

SIGNAGE SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ROUTE	STATION	LANE	SIDE	FACING	SIGN * MUTCD	SIZE		SIGN PANEL			MESSAGE	# OF POSTS	72800100	73000100	72700100	73400100
						W	H	TYPE 1	TYPE 2	TYPE 3			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	CONCRETE FOUNDATIONS
						SQ FT	SQ FT	SQ FT	FOOT	FOOT			POUND	CU YD		
FAP 322	667+64	SB	MEDIAN	NORTH	R3-1100L	36	36				LEFT TURN LANE	1	19.0			
					M6-2L	21	15	2.2			ARROW LT					
	667+91	SB	OUTSIDE	NORTH	R3-1100R	36	36	9.0			RIGHT TURN LANE	1	18.7			
					M6-2R	21	15	2.2			ARROW RT					
	669+60	SB	MEDIAN	NORTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	20.2			
					W16-8	36	15	3.8			ILLINOIS STREET					
			OUTSIDE	NORTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	19.9			
					W16-8	36	15	3.8			ILLINOIS STREET					
	674+00	NB	OUTSIDE	SOUTH	SIGN006	150	24			25.0	LAKE SHELBYVILLE ARROW	2		189	1.4	
	677+18	NB	MEDIAN	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	21.5			
					W16-8	36	30	7.5			TAYLORVILLE - FINDLAY					
			OUTSIDE	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	21.2			
					W16-8	36	30	7.5			TAYLORVILLE - FINDLAY					
	679+08	NB	OUTSIDE	SOUTH	R3-1100R	36	36	9.0			RIGHT TURN LANE	1	18.7			
					M6-2R	21	15	2.2			ARROW RT					
	679+36	NB	MEDIAN	SOUTH	R3-1100L	36	36	9.0			LEFT TURN LANE	1	19.0			
					M6-2L	21	15	2.2			ARROW LT					
	683+25	NB	MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	685+00	SB	OUTSIDE	NORTH	M3-3	24	12	2.0			SOUTH	1	17.4			
					M1-4	24	24	4.0			US ROUTE 51					
	686+00	NB	MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	686+58		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	687+79		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	688+25	SB	MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	689+00	NB	OUTSIDE	SOUTH	M3-1	24	12	2.0			NORTH	1	17.4			
					M1-4	24	24	4.0			US ROUTE 51					
	691+00	SB	MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	695+00	SB	MEDIAN	NORTH	R3-1100L	36	36	9.0			LEFT TURN LANE	1	19.0			
					M6-2L	21	15	2.2			ARROW LT					
	695+29	SB	OUTSIDE	NORTH	R3-1100R	36	36	9.0			RIGHT TURN LANE	1	18.7			
					M6-2R	21	15	2.2			ARROW RT					
	697+18	SB	MEDIAN	NORTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	21.5			
					W16-8	36	30	7.5			TAYLORVILLE - FINDLAY					
			OUTSIDE	NORTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	21.2			
					W16-8	36	30	7.5			TAYLORVILLE - FINDLAY					
	700+00	SB	OUTSIDE	NORTH	SIGN005	150	24			25.0	ARROW LAKE SHELBYVILLE	2		189	1.4	
	710+70	NB	MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	713+45	NB	MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	713+85		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	715+05		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	715+45	SB	MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	718+20	SB	MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	723+00	SB	MEDIAN	WEST	R6-1R	36	12	3.0			ONE WAY RT	1	15.7			
	723+00	NB	MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	15.7			
	731+89	NB	MEDIAN	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.9			
			OUTSIDE	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.6			
	733+78	NB	OUTSIDE	SOUTH	R3-1100R	36	36	9.0			RIGHT TURN LANE	1	18.7			
					M6-2R	21	15	2.2			ARROW RT					
	734+08	NB	MEDIAN	SOUTH	R3-1100L	36	36	9.0			LEFT TURN LANE	1	19.0			
					M6-2L	21	15	2.2			ARROW LT					
	738+00	NB	MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	739+50	SB	OUTSIDE	NORTH	M3-3	24	12	2.0			SOUTH	1	17.4			
					M1-4	24	24	4.0			US ROUTE 51					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SIGNAGE
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY

SCALE: NONE
 DATE: 8/22/06

DRAWN BY: SEB
 CHECKED BY: TLD

CONTINUED ON NEXT SHEET

Mg-15-2018 01/14/14/09/04

S:FILE