

SIGNAGE SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ROUTE	STATION	LANE	SIDE	FACING	SIGN * MUTCD	SIZE		SIGN PANEL			MESSAGE	# OF POSTS	72000100	72000200	72000300	72800100	73000100	72700100	73400100	
						W	H	TYPE 1	TYPE 2	TYPE 3			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	CONCRETE FOUNDATIONS				
						SQ FT	SQ FT	SQ FT	FOOT	FOOT			POUND	CU YD						
FAP 322	740+75	NB	MEDIAN	NORTH	R5-1	36	36				DO NOT ENTER	1				17.7				
			OUTSIDE	NORTH	R5-1	36	36				DO NOT ENTER	1					17.4			
	741+29		MEDIAN	WEST	R6-1L	36	12				ONE WAY LT	1				17.4				
					R1-2	36					YIELD									
	742+50		MEDIAN	EAST	R6-1L	36	12				ONE WAY LT	1				17.4				
					R1-2	36					YIELD									
	743+00	SB	MEDIAN	SOUTH	R5-1	36	36				DO NOT ENTER	1				17.7				
					OUTSIDE	SOUTH	R5-1	36	36				DO NOT ENTER	1				17.4		
	744+00	NB	OUTSIDE	SOUTH	M3-1	24	12				NORTH	1				17.4				
					M1-4	24	24				US ROUTE 51									
	745+75	SB	MEDIAN	SOUTH	R5-1a	36	24				WRONG WAY	1				16.7				
					OUTSIDE	SOUTH	R5-1a	36	24				WRONG WAY	1				16.4		
	747+00	NB	OUTSIDE	SOUTH	R2-1	48	60		20.0		SPEED LIMIT 65 MPH	1				19.4				
	749+71	SB	MEDIAN	NORTH	R3-1100L	36	36				LEFT TURN LANE	1				19.0				
					M6-2L	21	15				ARROW LT									
	750+00	SB	OUTSIDE	NORTH	R3-1100R	36	36				RIGHT TURN LANE	1				18.7				
					M6-2R	21	15				ARROW RT									
	751+89	SB	MEDIAN	NORTH	W2-1	36	36				SIDE ROAD SYMBOL	1				18.9				
					OUTSIDE	NORTH	W2-1	36	36				SIDE ROAD SYMBOL	1				18.6		
	753+00	NB	OUTSIDE	SOUTH	SIGN004	108	36			27.0	MOWEAQUA 6 DECATUR 22	2					189		1.4	
	754+50	SB	OUTSIDE	NORTH	SIGN003	120	24		20.0		ASSUMPTION ARROW	2					189		1.4	
	758+80	NB	MEDIAN	EAST	R6-1R	36	12				ONE WAY RT	1				15.7				
	762+04	NB	MEDIAN	SOUTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1				18.9				
					OUTSIDE	SOUTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1				18.6		
	764+10	NB	MEDIAN	SOUTH	R3-1100L	36	36				LEFT TURN LANE	1				19.0				
					M6-2L	21	15				ARROW LT									
	768+25	NB	MEDIAN	NORTH	R5-1a	36	24				WRONG WAY	1				16.7				
					OUTSIDE	NORTH	R5-1a	36	24				WRONG WAY	1				16.4		
771+25	NB	MEDIAN	NORTH	R5-1	36	36				DO NOT ENTER	1				17.7					
				OUTSIDE	NORTH	R5-1	36	36				DO NOT ENTER	1				17.4			
771+54		MEDIAN	WEST	R6-1L	36	12				ONE WAY LT	1				17.4					
				R1-2	36					YIELD										
772+53		MEDIAN	EAST	R6-1L	36	12				ONE WAY LT	1				17.4					
				R1-2	36					YIELD										
772+84	SB	MEDIAN	SOUTH	R5-1	36	36				DO NOT ENTER	1				17.7					
				OUTSIDE	SOUTH	R5-1	36	36				DO NOT ENTER	1				17.4			
775+84	SB	MEDIAN	SOUTH	R5-1a	36	24				WRONG WAY	1				16.7					
				OUTSIDE	SOUTH	R5-1a	36	24				WRONG WAY	1				16.4			
782+04	SB	MEDIAN	NORTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1				18.9					
				OUTSIDE	NORTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1				18.6			
TR229A	19+20		RT	EAST	R6-1L	36	12			ONE WAY LT	2				38.6					
				WEST	R6-1R	36	12			ONE WAY RT										
				WEST	R1-1	36	36			STOP										
				WEST	R6-3a	24	18			DIVIDED HIGHWAY										
20+80			LT	WEST	R6-1L	36	12			ONE WAY LT	2				38.6					
				EAST	R6-1R	36	12			ONE WAY RT										
				EAST	R1-1	36	36			STOP										
				EAST	R6-3a	24	18			DIVIDED HIGHWAY										
ASSUMPTION SOUTH CONNECTOR	3+30		LT	EAST	R6-1L	36	12			ONE WAY LT	2				38.6					
				WEST	R6-1R	36	12			ONE WAY RT										
				WEST	R1-1	36	36			STOP										
				WEST	R6-3a	24	18			DIVIDED HIGHWAY										
SERVICE DRIVE 614	3+00		RT	WEST	W1-7	48	24			DOUBLE ARROW	2				32.8					
				EAST	W14-1	30	30			DEAD END	1					17.9				
ILLINOIS STREET	4+06		RT	WEST	R1-1	36	36			STOP	1				17.2					
				WEST	W3-1a	30	30			STOP AHEAD SYMBOL	1					17.9				
50+08			RT	EAST	R6-1L	36	12			ONE WAY LT	2				38.6					
				WEST	R6-1R	36	12			ONE WAY RT										
				WEST	R1-1	36	36			STOP										
				WEST	R6-3a	24	18			DIVIDED HIGHWAY										
TR 209	51+54		LT	WEST	R6-1L	36	12			ONE WAY LT	2				38.6					
				EAST	R6-1R	36	12			ONE WAY RT										
				EAST	R1-1	36	36			STOP										
				EAST	R6-3a	24	18			DIVIDED HIGHWAY										

CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SIGNAGE
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY

SCALE: NONE
 DATE: 8/22/06

DRAWN BY: SEB
 CHECKED BY: TLD

Mo-15-2018 014454204

SFILE4