

**SCHEDULE  
COMBINATION CURB AND GUTTER REMOVAL**

LOCATION	QUANTITY
	FOOT
STA. 9+00.85 (IL. 121) TO STA. 56+35 (IL. 10) RT.	150
STA. 6+82 (IL. 121) TO STA. 57+08 (IL. 10) LT.	260
TOTAL	410

**SCHEDULE  
PORTLAND CEMENT CONCRETE SIDEWALK 4"**

LOCATION	QUANTITY
	SQ. FT.
STA. 6+77 (IL. 121) TO STA. 56+61 LT.	916
STA. 8+90.85 (IL. 121) TO STA. 57+22 (IL. 10) RT.	1070
TOTAL	1986

**SCHEDULE  
PIPE CULVERTS, CLASS A, TYPE 1, RCCP 12"**

LOCATION	QUANTITY
	FOOT
STA. 55+55 14' LT. TO STA. 55+61 39' LT.	26
TOTAL	26

**SCHEDULE  
STORM SEWERS, CLASS A, TYPE 1, 15"**

LOCATION	QUANTITY
	FOOT
STA. 55+88 43.4' RT. TO STA. 56+05 60.2' RT.	24
STA. 56+05 60.2' RT. TO STA. 57+10 31.2 RT.	108
TOTAL	132

**SCHEDULE  
STORM SEWER REMOVAL**

LOCATION	QUANTITY
	FOOT
STA. 55+47 16' LT. TO 36' LT.	20
TOTAL	20

**SCHEDULE  
COMBINATION CONCRETE CURB AND GUTTER, TYPE B 6.18**

LOCATION	QUANTITY
	FOOT
STA. 9+01 (IL. 121) TO STA. 57+80.5 (IL. 10) RT.	267
STA. 6+82 (IL. 121) TO STA. 57+80.5 (IL. 10) LT.	331
TOTAL	598

**SCHEDULE  
DETECTABLE WARNINGS**

LOCATION	QUANTITY
	SQ. FT.
STA. 55+43 20' LT.	10
STA. 55+82 55' RT.	10
TOTAL	20

**SCHEDULE  
SUB-BASE GRANULAR MATERIAL, TYPE A 6"**

LOCATION	QUANTITY
	SQ. YD.
STA. 9+00.85 (IL. 121) TO STA. 57+80.5 RT. (IL. 10)	70
STA. 55+26 TO STA. 57+27.38 RT. (PAVEMENT)	212
STA. 55+26 TO STA. 56+36.81 LT. (PAVEMENT)	11
STA. 6+82 (IL. 121) TO STA. 57+80.5 (IL. 10) LT.	90
TOTAL	383

**SCHEDULE  
MEDIAN SURFACE REMOVAL**

LOCATION	QUANTITY
	SQ. FT.
STA. 2+08.5 TO STA. 3+52	731
STA. 11+33.5 TO STA. 13+04	775
STA. 47+52 TO STA. 48+06	237
STA. 56+85 TO STA. 57+47	255
TOTAL	1998

**SCHEDULE  
TRENCH BACKFILL**

LOCATION	QUANTITY
	CU. YD.
STA. 55+73 TO STA. 56+05 RT. (IL. 10)	4
STA. 56+05 TO STA. 57+10 RT. (IL. 10)	23
STA. 55+55 TO STA. 55+61 LT. (IL. 10)	5
TOTAL	32

**SCHEDULE  
PORTLAND CEMENT CONCRETE BASE COURSE 9"**

LOCATION	QUANTITY
	SQ. YD.
STA. 55+26 TO STA. 57+27.38 RT.	212
STA. 55+26 TO STA. 56+36.81 LT.	12
MEDIAN AREAS	222
TOTAL	446

**SCHEDULE  
SIDEWALK REMOVAL**

LOCATION	QUANTITY
	SQ. FT.
STA. 55+66 TO STA. 57+22 RT.	500
STA. 6+77 (IL. 121) TO STA. 56+61 (IL. 10) LT.	1117
TOTAL	1617

**SCHEDULE  
PRECAST REINFORCED CONCRETE END SECTIONS 12"**

LOCATION	QUANTITY
	SQ. FT.
STA. 55+61 39' LT.	1
TOTAL	1

**SCHEDULE  
ESTIMATED QUANTITIES FOR COMBINATION  
CURB AND GUTTER REMOVAL AND REPLACEMENT  
& MEDIAN SURFACE REMOVAL AND REPLACEMENT**

LOCATION	COMB. CURB & GUTTER REMOVAL & REPLACEMENT	MEDIAN SURFACE REMOVAL & REPLACEMENT
	FOOT	SQ. FT.
ENTIRE PROJECT ESTIMATE	1144	1260
TOTAL	1144	1260

**SCHEDULE  
PAVEMENT PATCHING TYPE III, 14"**

LOCATION	QUANTITY
	SQ. YD.
STA. 2+09, BOTH LANES, 1 PATCH @ 23 SQ. YD. & 1 PATCH @ 20 SQ. YD.	43
STA. 11+60, BOTH LANES, 2 PATCHES @ 19 SQ. YD. EACH	38
TOTAL	81

**SCHEDULE  
CLASS C PATCHES, TYPE III, 14"**

LOCATION	QUANTITY
	SQ. YD.
SOUTHBOUND STA. 57+58, BOTH LANES, 2 PATCHES @ 20 SQ. YD. EACH	40
NORTHBOUND STA. 57+58, BOTH LANES, 2 PATCHES @ 20 SQ. YD. EACH	40
TOTAL	80

**SCHEDULE  
AGGREGATE WEDGE SHOULDER, TYPE B**

LOCATION	QUANTITY
	TON
STA. 50+54 TO STA. 57+50 (EAST SIDE)	16.5
STA. 50+59 TO STA. 57+50 (WEST SIDE)	16.5
TOTAL	33

**SCHEDULE  
WATER VALVES TO BE ADJUSTED**

LOCATION	QUANTITY
	EACH
STA. 52+29, 22' LT.	1
STA. 52+40, 56' LT.	1
STA. 55+69, 10' LT.	1
STA. 56+12, 12' RT.	1
STA. 56+12, 28' LT.	1
STA. 60+01, 34' RT.	1
STA. 60+11, 11' LT.	1
STA. 39+06, 16' RT.	1
STA. 41+42, 17' RT.	1
TOTAL	9

**SCHEDULE  
MANHOLES TO BE ADJUSTED**

LOCATION	QUANTITY
	EACH
STA. 52+09, 26' RT.	1
STA. 52+16, 2' RT.	1
STA. 52+69, 25' RT.	1
STA. 55+53, 21' RT.	1
STA. 56+02, 2' RT.	1
STA. 57+60, 15' RT.	1
STA. 59+31, 18' RT.	1
STA. 59+82, 1' RT.	1
STA. 60+30, 15' RT.	1
STA. 0+05, 18' RT.	1
STA. 1+68, 26' RT.	1
STA. 26+38, 27' RT.	1
STA. 30+34, 5' RT.	1
STA. 36+04, 1' RT.	1
STA. 39+25, 15' RT.	1
STA. 39+53, 6' RT.	1
STA. 40+55, 9' RT.	1
STA. 42+78, 7' RT.	1
STA. 43+13, 10' LT.	1
STA. 46+36, 11' LT.	1
STA. 46+54, 3' RT.	1
STA. 49+82, C	1
STA. 50+38, 16' LT.	1
TOTAL	23

FILE NAME = e:\pwwork\pwwid001\LAUGHLIN\RL\0181122\d72998-ah-schedule.dgn  
 USER NAME = laughlinr1  
 PLOT SCALE = 2.0000' / IN.  
 PLOT DATE = Mar-18-2010 02:16:40PM

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -



**Allen Henderson & Associates, Inc.**  
 Civil and Structural Engineers Springfield, IL  
 62703 Phone: (217)544-8033 IL Design Firm  
 No. 184-001907

**QUANTITY SCHEDULES**

SCALE: SHEET NO. 9 OF 32 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	(242)RS-4116 RS-5	LOGAN	32	9
CONTRACT NO. 72998				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				