

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100%	I-72			SCOTT I-72		MORGAN I-72				
			STATE	SCOTT CO. FAI 72 (I-72) ROADWAY 1000	MORGAN CO. FAI 72 (I-72) ROADWAY 1000	MORGAN CO. BL-72/US 67 ROADWAY 1000	STRUCTURE SN 086-0023 SFTY-2A	STRUCTURE SN 086-0024 SFTY-2A	STRUCTURE SN 069-0054 SFTY-2A				
50102400	CONCRETE REMOVAL	CU YD	25.2				12.6	12.6					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25.2				12.6	12.6					
50300300	PROTECTIVE COAT	SQ YD	66				33	33					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4100				2050	2050					
50800515	BAR SPLICERS	EACH	56				28	28					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	180				90	90					
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1200			1200							
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4			4							
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4			4							
64200105	SHOULDER RUMBLE STRIP	FOOT	174306	61244	78186	34876							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16									
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33							
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2									
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3		2	1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.34	0.33	0.33							
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.34	0.33	0.33							
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.34	0.33	0.33							
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	39	17	19	3							
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	2	2	2							
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	27684	10450	13362	3872							
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	197162	69867	87959	39336							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3508	1230	1573	705							
70400100	TEMPORARY CONCRETE BARRIER	FOOT	650	650									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	650	650									
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	21798	7655	9773	4370							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1308	383	489	436							
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18			18							
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	52	52									
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4			4							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1435	1435									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1308	383	489	436							

* SPECIALTY ITEM

FILE NAME = c:\pwwork\PIWIDOT\LAUGHLIN\l\ms24453\672A16-sht-S00.DGN	USER NAME = laughlinr1	DESIGNED -	REVISED -
Johnson, Depp & Gulsberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20.0000' / IN. PLOT DATE = Apr-06-2010 09:56:31AM	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

* 86-10RS-3, 69-6RS-2, 69-1RS ** SCOTT, MORGAN				
SHEET NO. 2 OF 3				
F.A.I. RTE. 72	SECTION .	COUNTY ..	TOTAL SHEETS 48	SHEET NO. 4
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT CONTRACT NO. 72A16				