

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100%	I-72			SCOTT I-72		MORGAN I-72			
			STATE	SCOTT CO. FAI 72 (I-72) ROADWAY 1000	MORGAN CO. FAI 72 (I-72) ROADWAY 1000	MORGAN CO. BL-72/US 67 ROADWAY 1000	STRUCTURE SN 086-0023 SFTY-2A	STRUCTURE SN 086-0024 SFTY-2A	STRUCTURE SN 069-0054 SFTY-2A			
X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	360	124	158	78						
X0322279	OUTLET MARKER	EACH	360	124	158	78						
X0322729	MATERIAL TRANSFER DEVICE	TON	49312	17318	22107	9887						
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	68						68			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH =< 5 INCHES)	SO FT	9					9				
X0325739	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SO YD	1000			1000						
X0350800	BOLLARDS	EACH	126	50	46	30						
X0350810	BOLLARD REMOVAL	EACH	59	26	33							
X2503000	MAINTENANCE MOWING	ACRE	131	47	55	29						
X7030072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	174398	61246	78186	34966						
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	0.5	0.5							
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	175364	62212	78186	34966						
Z0030240	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2								
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2								
Z0075310	TIE BARS 3/4"	EACH	135	35	81	19						

* SPECIALTY ITEM

• 86-10RS-3, 69-6RS-2, 69-1RS
 ** SCOTT, MORGAN **SHEET NO. 3 OF 3**

FILE NAME :	USER NAME : laughtinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.J. RTE. 72	SECTION .	COUNTY ..	TOTAL SHEETS 48	SHEET NO. 5
Johnson, Depp & Oulsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20,0000' / IN. PLOT DATE = Apr-06-2010 09:56:48AM	DRAWN -	REVISED -			SCALE:		SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 72A16
						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				