

CLASS A PATCHES, TYPE II, 8 INCH
 CLASS A PATCHES, TYPE III, 8 INCH
 CLASS A PATCHES, TYPES IV, 8 INCH
 CLASS A PATCHES, TYPE II, 12 INCH
 CLASS A PATCHES, TYPE III, 12 INCH
 CLASS A PATCHES, TYPES IV, 12 INCH
 PATCHING REINFORCEMENT
 SAW CUTS
 TIE BARS 3/4"
 (ALL PATCHES IN DRIVING LANE)

LOCATION	TYPE II 8" SQ YD 5 TO <15	TYPE III 8" SQ YD 15 TO <25	TYPE IV 8" SQ YD 25>	TYPE II 12" SQ YD 5 TO <15	TYPE III 12" SQ YD 15 TO <25	TYPE IV 12" SQ YD 25>	PATCHING REINFORCEMENT (SQ. YD.)	SAW CUTS (FOOT)	TIE BARS (EACH)
FAI-72 (SCOTT COUNTY) WB LANES									
STA. 110+62				8			8	60	
STA. 110+87				8			8	60	
STA. 113+24				8			8	60	
STA. 113+58				10.7			10.7	64	
STA. 114+16						65.3	65.3	146	24
STA. 115+01				8			8	60	
STA. 115+44				8			8	60	
STA. 122+07				8			8	60	
STA. 143+94					24		24	84	
STA. 145+14					16		16	72	
STA. 154+48				8			8	60	
STA. 164+52				8			8	60	
STA. 183+81				8			8	60	
STA. 186+86				8			8	60	
STA. 209+05				8			8	60	
STA. 211+62				8			8	60	
STA. 212+07				8			8	60	
STA. 212+73				8			8	60	
STA. 215+48				8			8	60	
STA. 225+54				8			8	60	
STA. 248+55				8			8	60	
STA. 261+43				8			8	60	
STA. 261+66				8			8	60	
EB LANES									
STA. 107+53					22.7		22.7	82	
STA. 137+62				8			8	60	
STA. 155+90						32	32	96	11
STA. 158+59				8			8	60	
STA. 251+83				8			8	60	
STA. 253+88				10.7			10.7	64	
STA. 254+12				8			8	60	
STA. 258+36				8			8	60	
(MORGAN COUNTY) WB LANES									
STA. 265+91				8			8	60	
STA. 313+41				8			8	60	
STA. 397+91						32	32	96	11
STA. 398+27						58.7	58.7	136	21
STA. 398+75				8			8	60	
STA. 399+72					16		16	72	
STA. 402+17				8			8	60	
STA. 403+17					20		20	78	
EB LANES									
STA. 307+27				10.7			10.7	64	
STA. 329+01					22.7		22.7	82	
STA. 330+02				8			8	60	
STA. 335+56						132	132	246	49
STA. 336+85				8			8	60	
STA. 367+37				8			8	60	
STA. 375+49				8			8	60	
STA. 399+06				8			8	60	
STA. 442+76					16		16	72	
ESTIMATED 25%				296.1					
BL-72/US 67									
NB LANES									
STA. 356+10	10.7						10.7	64	
STA. 407+30	13.3						13.3	68	
STA. 407+60		16					16.0	72	
STA. 408+10	14.7						14.7	70	
STA. 453+95				53.3			53.3	128	19
TOTALS =	38.7	16		53.3	370.2	320	861.5	3836	135

ESTIMATED QUANTITIES				
PAY ITEM NUMBER	PAY ITEM	UNIT	QUANTITY	LOCATION/ REASON
44212899	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	800	AS DIRECTED
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	150	AS DIRECTED
X0325739	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	1000	SHOULDER FAILURE DURING CONSTRUCTION

WIDTH RESTRICTION SIGNING

LOCATION	L SUM
FAI 72 (SCOTT COUNTY)	0.50
(MORGAN COUNTY)	0.50
TOTAL =	1

URETHANE PAVEMENT MARKING - LINE 5"

LOCATION	EDGELINE SOLID WHITE FOOT	CENTERLINE SKIP-DASH WHITE FOOT	EDGELINE SOLID YELLOW FOOT
FAI-72 (SCOTT COUNTY)			
WB STA. 107+16.06 TO STA. 262+29.22	15,513	50	15,513
EB STA. 106+86.47 TO STA. 262+29.22 (MORGAN COUNTY)	15,543	50	15,543
WB STA. 262+29.22 TO STA. 443+19.48	18,090		18,090
EB STA. 262+29.22 TO STA. 443+19.48	18,090		18,090
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH			
WB STA. 10+03.94 TO STA. 22+74.37	1270		1270
EB STA. 10+03.94 TO STA. 26+47.25	1643		1643
BL-72/US 67			
NB STA. 356+25 TO STA. 453+98	9773		9773
SB STA. 372+50 TO STA. 449+60	7710		7710
SUB TOTALS =	87,632	100	87,632
TOTAL =	175,364		

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	EACH
FAI-72 (SCOTT COUNTY)	
STAGE I, (SN 086-0023/24)	
RT. STA. 197+05	1
LT. STA. 202+95	1
TOTAL =	2

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3

LOCATION	EACH
FAI-72 (SCOTT COUNTY)	
STAGE II, (SN 086-0023/24)	
RT. STA. 197+06	1
LT. STA. 202+91.5	1
TOTAL =	2

• 86-10RS-3, 69-6RS-2, 69-1RS
 •• SCOTT, MORGAN