

GENERAL NOTES:

- 1 ALL ELEVATIONS SHOWN IN THE PLANS ARE U. S. G. S. MEAN SEA LEVEL DATUM.
- 2 ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- 3 THE LOCATION OF THOSE BURIED AND ABOVE GROUND UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE J. U. L. I. E. NUMBER IS (800) 892-0123. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED, SEE SPECIAL PROVISIONS FOR STATUS OF UTILITIES, WITH UTILITY COMPANIES LISTED.
- 4 THE EXISTING ROAD SIGNS THAT INTERFERE WITH CONSTRUCTION SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. AFTER THE CONSTRUCTION IS COMPLETE, THE CONTRACTOR SHALL REPLACE THE SIGNS AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT CONSIDERED INCLUDED IN THE CONTRACT UNIT BID PRICES.
- 5 ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH THE CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF RIGHT-OF-WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT BID PRICE FOR EARTH EXCAVATION. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 6 THE FOLLOWING APPLICATION RATES WERE USED FOR QUANTITY CALCULATIONS:
 

LEVELING BINDER	0.056 TON/SQ YD • in
BIT. CONC. SURF. CSE	0.056 TON/SQ YD • in
AGG. SHLDS./BASE CSE.	2.05 TON/CU.YD
BIT. MATLS. (PR COAT)	0.00038 TON/SQ YD
AGG. (PR COAT)	0.001425 TON/SQ YD
- 7 ACCESS TO ALL PROPERTIES SHALL BE MAINTAINED DURING CONSTRUCTION ACTIVITIES. WHEN UNAVOIDABLE, REASONABLE PARKING SHALL BE PROVIDED FOR THOSE PROPERTIES WHICH ARE TEMPORARILY UNACCESSIBLE.
- 8 THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE DISTRICT 6 OPERATIONS 14 DAYS IN ADVANCE OF ANY WORK TO VERIFY THE LOCATION OF ANY PASSING ZONES.

STANDARDS:

000001-05	
442201-03	
630001-08	
635006-03	
635011-02	704421-02
701001-02	701422-02
701006-03	
701011-02	
701901-01	
780001-02	
781001-03	

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMENTS WERE MADE.

1. THE RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS CONCERNING ANY MAJOR PLAN CHANGES.
2. INFORMATIONAL LETTER WITH THE CITY OF LINCOLN
3. RAILROAD LIABILITY INSURANCE SHALL BE OBTAINED BY THE CONTRACTOR.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE:

MIXTURE USE(S):	HMA SURFACE	LEVELING BINDER	INCIDENTAL HMA SURFACING	HMA SHOULDERS	HMA PATCHING
PG	PG 64-22	PG 64-22	PG 64-22	PG 58-22	PG 64-22
DESIGN AIR VOIDS	4.0% @ N70	4.0% @ N70	4.0% @ N50	2.0% @ N30	4.0% @ N70
MIXTURE COMPOSITION (GRADATION MIXTURE)	IL 9.5 OR 12.5	IL 9.5	IL 9.5 OR 12.5	BAM (OTHER)	IL 19.0
FRICTION AGGREGATE	MIX D	N/A	MIX C	N/A	N/A

Route \_\_\_\_\_  
 Section \_\_\_\_\_  
 County \_\_\_\_\_

DISTRICT SIX	
EXAMINED	<u>MARCH 30</u> 20 <u>10</u>
<i>[Signature]</i>	
OPERATIONS ENGINEER	

EXAMINED	<u>MARCH 26</u> 20 <u>10</u>
<i>[Signature]</i>	
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED	<u>April 9</u> 20 <u>10</u>
<i>[Signature]</i>	
PROGRAM DEVELOPMENT ENGINEER	

• FAS 1773/ FAU 7706

FILE NAME =	USER NAME = vareende	DESIGNED -	REVISED -
at\p\work\p\dot\vereende\0151693\067	A44-shr-gemote.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-08-2010 05:37:01PM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GENERAL NOTES**

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	21RS-4.22RS-5	LOGAN	31	2
CONTRACT NO. 72A44				
ILLINOIS FED. AID PROJECT				