

RESURFACING SCHEDULE														
Sta to Sta	Length	Avg. Pav. W	Parking Area	Pav. Area	Bit Mat Prime Coat	Agg Prime Coat	HMA Surface	HMA Surf Rem	Leveling Binder	Agg Shoulder	Grade & Shape Shld	Butt Joint	Temp Ramps	
	(FT)	(FT)	(FT)	(SY)	(TON)	(TON)	(TON)	(SY)	(TON)	(TON)	(FT)	(SY)	(SY)	
MAINLINE														
US 54														
+20	1+90	170	52	--	982	0.7	3.9	83	809	41	--	--	173.3	28.9
+28	+45	17	44	--	82	0.1	0.3	7	34	3	--	--	48.3	24.2
IL 106														
9+00	7+57	143	56	--	890	0.7	3.6	75	704	37	--	--	186.7	31.1
STA EQN 1000+00.00BK = 7+56.90AH														
1000+00	1000+90	90	52	--	520	0.4	2.1	44	520	22	--	--	--	--
1033+29	1046+30	1,301	26	--	3,758	2.9	15.0	316	3,758	158	74	26	--	--
1046+30	1050+35	405	26	--	1,170	0.9	4.7	98	1,170	49	12	8	--	--
1050+35	1058+85	850	26	--	2,456	1.9	9.8	206	2,456	103	24	17	--	--
1058+85	1059+97	112	26	--	324	0.1	1.3	27	324	14	3	2	--	--
1059+97	1061+86	189	26	--	546	0.4	2.2	46	546	23	11	4	--	--
1061+86	1066+59	473	26	--	1,366	1.0	5.5	115	1,366	57	13	9	--	--
1066+59	1075+09	850	26	--	2,456	1.9	9.8	206	2,456	103	24	17	--	--
1075+09	1076+00	91	26	--	263	0.2	1.1	22	263	11	5	2	--	--
1076+00	1078+00	200	26	--	578	0.4	2.3	49	578	24	11	4	--	--
1078+00	1089+56	1,156	26	--	3,341	0.1	13.4	281	3,341	140	66	23	--	--
1089+56	1100+23	1,067	26	--	3,082	2.3	12.3	259	3,082	129	61	21	--	--
1100+23	1100+39	16	26	--	46	0.1	0.2	4	46	2	1	0.3	--	--
1100+39	1117+78	1,739	26	--	5,024	3.8	20.1	422	5,024	211	--	--	--	--
1117+78	1124+37	659	30	--	2,198	1.7	8.8	185	2,198	92	38	13	--	--
1124+37	1125+06	69	30	--	229	0.2	0.9	19	229	10	4	1	33.3	16.7
OMISSION: STA. 1125+06 TO STA. 1126+53														
1126+53	1134+75	822	28	--	2,557	1.9	10.2	215	2,557	107	47	16	31.1	15.6
1134+75	1136+78	203	26	--	585	0.4	2.3	49	585	25	12	4	--	--
1136+78	1137+00	23	26	--	65	0.1	0.3	5	65	3	1	45	--	--
STA.EQN 1137+00.00BK = 131+55.25AH														
131+55	140+30	875	26	--	2,527	1.9	10.1	212	2,527	106	50	17	--	--
140+30	141+50	120	26	--	346	0.3	1.4	29	346	15	7	2	--	--
141+50	146+79	529	26	--	1,529	0.1	6.1	128	1,529	64	30	11	--	--
146+79	148+09	130	26	--	375	0.3	1.5	31	375	16	7	3	--	--
148+09	152+36	428	26	--	1,236	0.9	4.9	104	1,236	52	24	9	--	--
152+36	154+70	234	26	--	675	0.5	2.7	57	675	28	13	5	--	--
154+70	175+00	2,030	26	--	5,864	4.5	24.0	493	5,864	246	116	41	86.67	14.44
PARKING AREA														
1000+90	1033+29	3,239	26	5,758	9,357	4.4	23.0	726	5,758	--	--	--	--	--
PARKING AREA TOTAL						4.4	23.0	726	5,758	--	0.0	0.0	0.0	0.0
MAINLINE TOTAL						31	181	3786	44660	1893	654	301	560	131
JOB TOTAL						35	204	4,512	50,418	1,893	654	301	560	131
PAVEMENT PATCHING														
Type	(SY)													
TY II	645													
TY III	350													
TY IV	300													