

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	100% STATE 1000
CODE NO	ITEM	UNIT		
20800150	TRENCH BACKFILL	CU YD	10	10
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	22	22
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	15.6	15.6
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21.5	21.5
40600300	AGGREGATE (PRIME COAT)	TON	109	109
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1843.2	1843.2
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3902.6	3902.6
40600990	TEMPORARY RAMP	SQ YD	591	591
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3714	3714
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	616.8	616.8
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	578	578
42400800	DETECTABLE WARNINGS	SQ FT	108	108
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	26334	26334
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	23737	23737
44000600	SIDEWALK REMOVAL	SQ FT	614	614
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	35	35
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	155	155
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	133	133
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	45	45
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	90	90
48101200	AGGREGATE SHOULDERS, TYPE B	TON	147.5	147.5
48203006	HOT-MIX ASPHALT SHOULDERS, 2 1/4"	SQ YD	4287.2	4287.2
50105220	PIPE CULVERT REMOVAL	FOOT	23	23
550A0050	STORM SEWERS, CLASS A, TYPE I 12"	FOOT	23	23
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1
60255500	MANHOLES TO BE ADJUSTED	EACH	33	33
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	75	75
64200105	SHOULDER RUMBLE STRIP	FOOT	7050	7050
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12

FILE NAME = c:\p\m\p\k\p\DOT\LAUGH\NRL\681789\0672C18-INT-500.dgn

USER NAME = laughlrvr1	DESIGNED -	REVISED -
DRAWN -	CHECKED -	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = Apr-14-2010 07:36:10AM	DATE -	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. 1 OF 2 SHEETS	STA. N/A	TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8139	(30)JRS-3	MACOUPIN	45	3
CONTRACT NO. 72C18				
ILLINOIS FED. AID PROJECT				