

CODE NO.	ITEM	UNIT	URBAN	FAP 658	FAP 662	FAP 666
			CONSTRUCTION CODE: 1000			
			FUNDING: 100% STATE			
			TOTAL	SECTION "A" OLD IL 29	SECTION "B" IL 4	SECTION "C" PEORIA RD
20200100	EARTH EXCAVATION	CU YD	996	--	996	--
20201006	GRADING AND SHAPING SHOULDERS	UNIT	363	--	363	--
25000200	SEEDING, CLASS 2	ACRE	0.23	--	0.23	--
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14.35	--	14.35	--
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14.35	--	14.35	--
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14.35	--	14.35	--
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.32	--	0.32	--
25100125	MULCH, METHOD 3	ACRE	0.23	--	0.23	--
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	--	200	--
28000500	INLET AND PIPE PROTECTION	EACH	24	--	24	--
28100105	STONE RIPRAP, CLASS A3	SQ YD	61	--	61	--
28200200	FILTER FABRIC	SQ YD	61	--	61	--
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	1,965	--	1,965	--
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	882	--	882	--
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	3,636	--	3,636	--
40300700	PREPARATION OF BASE	SQ YD	3,030	1,698	--	1,332
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	113	43	49	21
40600300	AGGREGATE (PRIME COAT)	TON	561	218	236	107
40600635	LEVELING BINDER (MACHINE METHOD), N7D	TON	7,832	5,073	1,138	1,621
40600895	CONSTRUCTING TEST STRIP	EACH	2	0.67	0.67	0.66
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,766	3,155	700	911
40600990	TEMPORARY RAMP	SQ YD	892	518	262	112
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N7D	TON	9,330	6,824	--	2,506

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
ct:\pwork\PM\DOT\LAUGHLINR1\dms47710\072C35-shl-500.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000 / 1 IN.		CHECKED -	REVISED -
PLOT DATE = Apr-30-2010 09:12:48AM		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	*	SANGAMON	206	4
CONTRACT NO. 72C35			ILLINOIS FED. AID PROJECT	