

SIDE ROAD PAVEMENT MARKING																
DESCRIPTION	STATION TO STATION		REFL. PVT MKRS		THERMOPLASTIC				PERFORMED PLASTIC TYPE B - INLAID				SHORT TERM PAVEMENT MARKING			WRKZNE PVT MKG REM.
			(EACH)	(EACH)	5" EOP (FT)	5" SKIP DASH (FT)	8" (FT)	12" (FT)	24" STOP BARS (FT)	LETTERS & SYM. (SQ FT)	5" (FT)	6" (FT)	EDGE OF PAVEMENT (FT)	CENTER LINE (FT)	STOP BAR (FT)	
BROWNING RD																
MAIN LINE	29+49	31+30	2	2	362	--	190	80	12	31.2		242	7	9	72	15
TURN LANE	29+49	31+30	2	2	--			--	18	31.2		--	--	--	108	18
YATES AVE																
EAST	10+33	10+53	--	--	--			--	12	--		--	--	--	72	12
WEST	9+56	9+66	--	--	--			--	12	--		--	--	--	72	12
MAPLE AVE																
MAIN LINE	10+34	10+54	--	--	--			--	20	--		--	--	--	120	20
N. GRAND AVE. EAST																
MAIN LINE	100+32	101+40	1	1	216	54	212	48	42	--	420	128	4	--	252	43
TURN LANE	100+32	100+80	1	1	--			--	18	--		72	--	--	108	18
TURN LANE	100+32	100+80	1	1	--			--	18	31.2		--	--	--	108	18
N. GRAND AVE. WEST																
MAIN LINE	+30	1+45	1	1	230	57.5	212	48	42		420	132	5	--	252	43
TURN LANE	1+60	15+30	17	17	--			--	18			72	--	--	108	18
TURN LANE	14+50	15+30	1	1	--			--	18	31.2		--	--	--	108	18
ELLIOT AVE.																
EAST	10+20	10+40	--	--	--			--	15	--		60	--	--	90	15
WEST	9+60	9+80	--	--	--			--	15	--		60	--	--	90	15
CALHOUN ST.																
EAST	100+20	100+40	--	--	--			--	20	--		80	--	--	120	20
WEST	99+60	99+80	--	--	--			--	20	--		58	--	--	120	20
HAY ST.																
MAIN LINE	100+20	100+40	--	--	--			--	12	--		60	--	--	72	12
DORLAN AVE																
MAIN LINE	100+20	100+40	--	--	--			--	12	--		60	--	--	72	12
HERNDON ST																
MAIN LINE	100+20	100+40	--	--	--			--	12	--		48	--	--	72	12
MILLER ST.																
EAST	100+20	100+42	--	--	--			--	21	--		106	--	--	126	21
WEST	100+20	100+46	--	--	--			--	16	--		64	--	--	96	16
CARPENTER ST.																
EAST	100+30	101+45	1	1	230	57.5	212	48	24	41.6		112			144	24
CARPENTER ST.																
WEST	100+28	100+56	--	--	--			--	16	--		78	--	--	96	16
REYNOLDS ST.																
MAIN LINE	100+25	100+55	--	--	--			--	16	--		74	--	--	96	16
MADISON ST. / MASON ST.																
MAIN LINE	100+25	100+55	--	--	--			--	52	--		208	--	--	312	52
													16	9	2886	
TOTAL			28	28	1038	169	826	224	481	166	840	1714	2911			485

FILE NAME =	et:\pw\work\PWIDOT\LAUGHLINRL\dms47710\0672C35-sht-schedule.dgn	DESIGNED -	REVISOR -
USER NAME =	laughlinr1	DRAWN -	REVISOR -
PLOT SCALE =	40.0000' / IN.	CHECKED -	REVISOR -
PLOT DATE =	Apr-30-2010 09:16:55AM	DATE -	REVISOR -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
SECTION "A" (IL 29)**

SCALE: SHEET NO. 7 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	*	SANGAMON	206	26
			CONTRACT NO. 72C35	
ILLINOIS FED. AID PROJECT				