

SECTION "B" - IL 4/VETERANS PKWY RESURFACING SCHEDULE																		
DESCRIPTION	STATION TO STATION		LENGTH	AVG. PAVT. WIDTH	PAVMENT AREA	EOP HMA SHLDR WIDTH	MEDIAN HMA SHLDR WIDTH	HMA SHLDR AREA	BIT MAT PRIMECOAT	AGG PRIMECOAT	LEVEL BINDER	2" POLY HMA SURFACE	HMA SURF. REM 2"	2" HMA SHLDR	AGG SHLDR	GRADE & SHAPE SHLDR	BUTT JOINT	TEMP RAMP
			(FT)	(FT)	(SQYD)	(FT)	(FT)	(SQYD)	(TON)	(TON)	(TON)	(TON)	(SQYD)	(TON)	(TON)	(UNIT)	(SQYD)	(SQYD)
SIDE ROAD -- 100 W. ROAD																		
MAIN LINE	+20	+88	68	45	340	--	--	--	0.3	0.7	--	38	318	--	--	--	22.2	14.8
MAIN LINE	8+75	9+17	42	45	210	--	--	--	0.2	0.4	--	24	188	--	--	--	22.2	14.8
SIDE ROAD -- BROWNING ROAD																		
MAIN LINE	16+85	17+89	104	43	491	--	--	--	0.2	1.0	--	55	447	--	--	--	44.4	29.6
SB RT TURN	16+85	17+67	82	26	231	--	--	--	0.1	0.5	--	26	231	--	--	--		
WB RT TURN	16+85	17+92	107	18	210	--	--	--	0.1	0.4	--	24	210	--	--	--		
MAIN LINE	19+10	20+27	117	43	553	--	--	--	0.2	1.1	--	62	508	--	--	--	44.4	29.6
EB RT TURN	19+12	20+27	115	25	319	--	--	--	0.1	0.6	--	36	319	--	--	--		
NB RT TURN	19+40	20+05	65	24	173	--	--	--	0.1	0.3	--	19	173	--	--	--		
SIDE ROAD -- 8TH STREET																		
MAIN LINE	47+65	48+97	132	24	352	--	--	--	0.1	0.7	--	39	293	--	--	--	58.9	39.3
SB RT TURN	47+65	48+97	132	26	379	--	--	--	0.1	0.8	--	42	379	--	--	--		
EB RT TURN	47+65	49+15	150	18	407	--	--	--	0.2	0.8	--	46	407	--	--	--		
MAIN LINE	50+20	51+65	145	32	508	--	--	--	0.2	1.0	--	57	480	--	--	--	27.8	18.5
NB RT TURN	50+30	51+10	80	32	276	--	--	--	0.1	0.6	--	31	276	--	--	--		
WB RT TURN	50+17	51+25	108	20	239	--	--	--	0.1	0.5	--	27	239	--	--	--		
SIDE ROAD TOTALS					4,687				2.0	9.4		525	4,467				220	147
NORTHBOUND TOTALS					30,172			16,846	18.0	93.6	75	3,379	46,858	1,887	498	180	240	58
SOUTHBOUND TOTALS					28,156			16,418	17.8	89.1	75	3,153	44,414	1,839	514	183	240	58
JOB TOTALS			9077		63,015			33,264	38	192	149	7,058	95,739	3,726	1,012	363	700	262

FILE NAME =	et:\pw\work\PWIDOT\LAUGHLINRL\dms47710\672C35-sht-schedule.dgn	DESIGNED -	REVISIED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SECTION "B" IL 4				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = laughlinr1		DRAWN -	REVISIED -		658	*	SANGAMON	206	28A				
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISIED -		SCALE: SHEET NO. 2A OF 7 SHEETS STA. TO STA.				CONTRACT NO. 72C35				
PLOT DATE = Apr-30-2010 09:17:18AM		DATE -	REVISIED -		ILLINOIS FED. AID PROJECT								