

SECTION "B" -- IL 4/VETERANS PKWY PAVEMENT MARKING SCHEDULE																				
DESCRIPTION	STATION TO STATION		LENGTH	SHORT-TERM			WORKZONE PAVT MKG REMOVAL	RAISED REFL PVT MKR	RAISED REFL. PAVT. MKR REM.	URETHANE PAVT MKG					PREFORMED PLASTIC PAVT MKG				THERMOPLASTIC	
				CENTERLINE PVT MKG	EDGE LN PVT MKG	24" STOP BAR (4"x6ea)				5" LINE YELLOW EOP	5" LINE WHITE EOP	8" WHITE MEDIAN	12" YELLOW CHEVRONS	12" WHITE CHEVRONS	5" SKIP DASH	6" LANE & SKIP LINES	24" STOP BARS	LTRS & SYMBOLS	8" LINE ISLANDS	12" LINE CHEVRONS
			(FT)	(FT)	(FT)	(FT)	(SQFT)	(EACH)	(EACH)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(SQFT)	(FT)	(FT)
IL 4 / 8TH ST. TURN LANES																				
LEFT TURN	270+26	266+00	426	--	42	--	7.0	--	--	426.00	--	--	--	--	--	58	--	--	--	--
LEFT TURN	268+00	266+00	200	--	--	--	--	12	12	--	--	400	--	80	--	--	--	31.2	--	--
LEFT TURN	266+00	264+25	175	--	22	84	3.7	--	--	175.00	175	--	--	--	--	14	31.2	--	--	--
RIGHT TURN	269+63	267+12	251	--	28	--	--	--	--	--	251	--	--	--	--	64	--	--	--	--
RIGHT TURN	267+12	264+90	222	--	26	--	--	7	7	--	222	--	--	--	--	222	--	46.8	--	--
IL 4 / BROWNING RD. TURN LANES																				
LEFT TURN	228+85	224+57	428	--	42	--	7.0	--	--	428.00	--	--	--	--	--	60	--	--	--	--
LEFT TURN	226+50	224+57	193	--	--	--	--	12	12	--	--	386	--	80	--	--	--	31.2	--	--
LEFT TURN	224+57	222+90	167	--	21	84	3.6	--	--	167.00	167	--	--	--	--	14	31.2	--	--	--
RIGHT TURN	227+27	225+50	177	--	22	--	--	--	--	--	177	--	--	--	--	44	--	--	--	--
RIGHT TURN	225+50	223+00	250	--	28	--	--	8	8	--	250	--	--	--	--	250	--	46.8	--	--
IL 4 / IL 29 TURN LANES																				
LEFT TURN	207+20	204+16	304	--	61	--	10.1	--	--	304.00	--	--	--	--	--	76	--	--	--	--
LEFT TURN	204+16	203+30	86	--	17	--	2.9	8	8	86.00	172	--	--	--	--	--	--	15.6	--	--
LEFT TURN	203+30	200+20	310	31	62	144	15.5	21	21	310.00	620	--	--	--	--	310	24	124.8	--	--
RIGHT TURN	206+60	204+16	244	--	49	--	8.1	--	--	--	244	--	--	--	--	61	--	--	--	--
RIGHT TURN	204+16	201+20	296	--	59	--	9.9	8	8	--	296	--	--	--	--	296	--	46.8	--	--
RIGHT TURN	201+20	552+85	90	--	--	108	--	--	--	--	90	--	--	--	--	--	18	15.6	240	150
IL 4 / IRWIN ST. TURN LANES																				
LEFT TURN	103+00	105+50	250	--	--	--	--	--	--	250.00	--	--	--	--	--	63	--	--	--	--
LEFT TURN	105+50	107+35	185	--	--	--	--	12	12	185.00	185	370	--	30	--	--	--	30.0	--	--
LEFT TURN	107+35	109+50	215	--	--	84	--	--	--	215.00	215	--	--	--	--	--	14	15.6	--	--
SOUTHBOUND TOTALS				1013	1436	1044	390.8	222	222	11661	13150	1246	580	190	2673	2690	174	512.8	240.0	150.0

SIDE ROAD -- IRWIN STREET																				
MAIN LINE	8+75	9+17	42	--	--	--	--	--	--	--	84	--	--	--	--	--	20	--	--	--
SIDE ROAD -- BROWNING ROAD																				
MAIN LINE	16+85	17+80	95	19	--	144	3.2	8	8	190	--	--	--	--	--	95	24	31.2	--	--
SB RT TURN	220+70	16+85	110	--	--	108	--	--	--	--	110	--	--	--	--	--	18	--	410	110
WB RT TURN	16+85	223+00	165	--	--	96	--	--	--	--	165	--	--	--	--	--	16	--	510	80
MAIN LINE	19+20	20+27	107	21	--	144	3.6	10	10	214	--	--	--	--	--	107	24	31.2	--	--
EB RT TURN	221+20	20+27	180	--	--	96	--	--	--	--	180	--	--	--	--	--	16	--	630	115
NB RT TURN	20+27	223+60	145	--	--	108	--	--	--	--	145	--	--	--	--	--	18	--	360	70
SIDE ROAD -- 8TH STREET																				
MAIN LINE	47+65	48+90	125	25	--	72	4.2	4	4	250	--	--	--	--	--	--	12	26.0	--	--
MAIN LINE	47+65	48+35	70	14	--	--	2.3	3	3	--	--	--	--	--	--	70	--	15.6	--	--
SB RT TURN	262+35	47+65	120	--	--	108	--	--	--	--	120	--	--	--	--	--	18	--	720	170
EB RT TURN	47+65	264+65	200	--	--	96	--	--	--	--	200	--	--	--	--	--	16	--	510	45
MAIN LINE	50+25	51+65	140	28	--	72	4.7	5	5	280	--	--	--	--	--	--	12	26.0	--	--
NB RT TURN	264+90	51+65	140	--	--	108	--	--	--	--	140	--	--	--	--	--	18	--	500	95
WB RT TURN	51+65	262+85	235	--	--	96	--	--	--	--	235	--	--	--	--	--	16	--	490	80
SIDE ROAD TOTALS				107	--	1,248	17.9	30	30	934	1379	--	--	--	--	272	228	130.0	4130.0	765.0
NORTHBOUND TOTALS				1,018	1,518	1,188	422.8	225	225	11,965	12727	1028	545	380	2705	1787	212	607.6	240.0	150.0
SOUTHBOUND TOTALS				1,013	1,436	1,044	390.8	222	222	11,661	13150	1246	580	190	2673	2690	174	512.8	240.0	150.0
JOB TOTALS				2,139	2,954	3,480	831	476	476	24,113	26696	2274	1125	570	5378	4749	614	1250	4610	1065