

SECTION "C" PEORIA RD. PAVEMENT MARKING SCHEDULE

DESCRIPTION	STATION TO STATION	LENGTH (FT)	URETHANE		THERMOPLASTIC		PREFORMED PLASTIC TYPE B - INLAID				SHORT TERM PAVEMENT MARKING			WORK ZONE PVT MKG REMOVAL					
			5" WHITE EDGE LINE FT	5" YELLOW EDGE LINE FT	5" YELLOW EDGE LINE FT	5" YELLOW SKIP DASH FT	24" WHITE STOP BARS FT	LETTERS & SYMBOLS SQ. FT.	2'x6'x6" SKIP DASH FT	5" WHITE SKIP DASH FT	RAISED REFL. PAVT MARKERS EA.	RAISED REFL. PAVT MARKER EA.	CENTERLINE FT	EDGE OF PAVEMENT FT	24" STOP BAR FT	EDGE OF PAVEMENT SQ. FT.			
NORTHBOUND LANES																			
MAIN LINE	52+40	52+50	10.00	--	--	10.00	--	--	--	--	3	4	4	1	9	--	2		
MAIN LINE	52+50	52+55	5.00	--	--	5.00	--	--	--	--	1	4	4	1	8	--	1		
MAIN LINE	52+55	78+45	2,590.12	--	--	2,590	--	--	--	--	648	65	65	259	215	--	79		
STA. EQN 78+45.12BK = 1+56.70AH																			
MAIN LINE	1+57	14+50	1,293.30	--	--	1,293	--	--	--	--	323	32	32	129	111	--	40		
MAIN LINE	14+50	15+17	67.25	--	--	67.25	--	--	--	--	17	2	2	7	13	--	3		
STA EQN 15+17.25BK = 144+00.00AH																			
MAIN LINE	144+00	151+34	734.00	--	--	744	144	--	62.4	--	184	18	18	73	68	--	23		
MAIN LINE	498+40	499+12	72.00	72	--	--	--	--	--	--	18	1	1	7	14	--	3		
MAIN LINE	499+12	500+86	174.41	174	--	--	--	--	--	--	44	2	2	17	22	--	7		
MAIN LINE	500+86	504+67	380.59	381	381	--	--	--	--	--	95	5	5	38	38	--	13		
MAIN LINE	504+67	505+84	117.00	117	--	--	--	--	--	--	29	1	1	12	17	--	5		
MAIN LINE	505+84	508+44	260.00	260	--	--	--	--	--	--	65	3	3	26	29	--	9		
MAIN LINE	508+44	512+74	430.00	430	430	--	--	--	--	--	108	5	5	43	42	--	14		
MAIN LINE	512+74	512+84	10.00	10	10	--	--	--	--	--	3	2	2	1	9	--	2		
PEORIA RD. / IL 4/VETERANS AVE. TURN LANES																			
LEFT/THROUGH TURN	151+34	152+72	138	138	138	--	--	--	--	35	--	2	2	--	19	--	3		
LEFT/THROUGH TURN	152+72	156+03	331	331	341	--	--	12	78	--	--	4	4	--	34	72	18		
RIGHT TURN	151+34	156+06	472	472	--	--	--	12	47	--	36	6	6	47	46	72	20		
RIGHT TURN	151+34	156+06	472	532	--	--	--	12	47	20	--	6	6	47	51	72	20		
PEORIA RD. / WATERWORKS RD. TURN LANES																			
LEFT TURN	504+10	505+84	174	--	174	--	--	--	--	44	--	--	--	--	--	--	--		
LEFT TURN	505+84	507+93	209	--	209	--	--	--	47	--	--	--	--	--	--	--	--		
NORTHBOUND TOTALS						2,917	1,683	4,710	144	36	281	99	1,572	162	162	709	746	216	262