

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS															
LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT. CONC. THICKNESS	BIT. SURF. REM. - BUTT JOINT	P. C. C. SURF. REM. - BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE SURFACE COURSE TY - B	BIT (P. C.)	AGG (P. C.)	INCIDENTAL BIT. SURF.
(LT / RT) (STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / BIT. / P. C. C.)	FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON
ILLINOIS 107															
LT. STA. 156+50	FE/RURAL	EARTH	24												
RT. STA. 157+80	FE/RURAL	EARTH	24												
LT. STA. 163+60	MB/RURAL														6
RT. STA. 163+70	PE/RURAL	AGG	12									1			4
RT. STA. 165+25	PE/RURAL	BIT/AGG	16					31					0.01		2
LT. STA. 165+60	MB/RURAL														6
LT. STA. 167+10	FE/RURAL	EARTH	24												
RT. STA. 167+25	FE/RURAL	EARTH	16												
LT. STA. 175+70	SR/MB/RURAL	BIT/AGG	12					27					0.01		11
LT. STA. 180+90	PE/MB/RURAL	BIT/AGG	12					27					0.01		9
LT. STA. 183+00	FE/RURAL	BIT/AGG	30												
LT. STA. 192+25	MB/RURAL														6
RT. STA. 192+25	SR/RURAL	AGG	12									1			12
LT. STA. 194+20	FE/RURAL	AGG	16												
LT. STA. 201+65	PE/MB/RURAL	BIT/AGG	10					25					0.01		9
RT. STA. 203+80	FE/RURAL	AGG	12												
LT. STA. 207+60	FE/RURAL	AGG	20												
LT. STA. 209+00	FE/RURAL	AGG	24												
RT. STA. 214+75	FE/RURAL	EARTH	10												
LT. STA. 216+00	MB/RURAL														6
RT. STA. 216+40	PE/RURAL	PCC	10						25				0.01		2
RT. STA. 217+20	FE/RURAL	BIT/AGG	24												
RT. STA. 218+05	FE/RURAL	BIT/AGG	16												
LT. STA. 218+40	FE/RURAL	AGG	18												
LT. STA. 223+60	PE/MB/RURAL	AGG	10									1			8
LT. STA. 225+15	PE/MB/RURAL	BIT	12					27					0.01		9
LT. STA. 228+50	PE/MB/RURAL	AGG	10									1			8
LT. STA. 238+30	SR/MB/RURAL	BIT/AGG	16					31					0.01		12
RT. STA. 238+30	SR/RURAL	O&C	20					35					0.01		3
LT. STA. 243+90	FE/RURAL	EARTH	20												
RT. STA. 244+00	PE/RURAL	BIT/AGG	12					27					0.01		2
RT. STA. 251+25	PE/RURAL	BIT/AGG	12					27					0.01		2
LT. STA. 251+70	MB/RURAL														6
RT. STA. 252+30	PE/RURAL	BIT	12					27					0.01		2
LT. STA. 252+50	FE/RURAL	EARTH	18												
RT. STA. 262+00	SR/RURAL	BIT	18					33					0.01		3
RT. STA. 265+20	FE/RURAL	EARTH	18												
LT. STA. 265+40	PE/MB/RURAL	BIT/AGG	12					27					0.01		9
RT. STA. 272+60	SR/RURAL	EARTH	12									1			12
RT. STA. 272+90	FE/RURAL	AGG	16												
LT. STA. 273+20	SR/RURAL	O&C	16					31					0.01		3
RT. STA. 286+90	FE/RURAL	AGG	12												
LT. STA. 299+55	PE/MB/RURAL	AGG	12									1			8
RT. STA. 299+55	FE/RURAL	EARTH	12												
LT. STA. 308+30	SR/RURAL	BIT	16					31					0.01		3
RT. STA. 312+70	PE/RURAL	AGG	12									1			4
TOTAL =								406	25			7	0.2		167

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED - 2/19/03 JCN
es:\pwwork\pwwid01\LAUGHLINRL\0200040\0672C37-shit-deta1.s.dgn		DRAWN - CADD	REVISED - 4/01/04 JCN
ENT PPP.DGN		CHECKED - JCN	REVISED -
		DATE - FEBRUARY 23, 1999	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**DIST. 6 DETAILS FOR RURAL/URBAN ENT., MAILBOX
TURNOUT & SIDEROADS W/O CONC. GUTTER (3P-PROJ.)**

SCALE: SHEET NO. 5 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
554	16(RS-6),18(RS-6),121(RS-5)	BROWN	49	38
CONTRACT NO. 72C37				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				