

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

				100% STATE
SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000-2A
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	18	18
35800100	PREPARATION OF BASE	SQ YD	123	123
35800200	AGGREGATE BASE REPAIR	TON	19	19
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	22	22
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	47.1	47.1
40600300	AGGREGATE (PRIME COAT)	TON	247	247
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,586	1,586
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,216	1,216
40600990	TEMPORARY RAMP	SQ YD	311	311
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7,742	7,742
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	133	133
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	42,378	42,378
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	38,186	38,186
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	50	50
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	100	100
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	100	100
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	50	50
48101200	AGGREGATE SHOULDERS, TYPE B	TON	698	698
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,174	1,174
48203100	HOT-MIX ASPHALT SHOULDERS	TON	247	247
* 63300575	REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	850	850
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1

				100% STATE
SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000-2A
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,081	8,081
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,201	1,201
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	65,653	65,653
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,035	1,035
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	452	452
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	611	611
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	135	135
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,116	1,116
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	33,589	33,589
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	452	452
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	611	611
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	32,065	32,065
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOL	SQ FT	1,201	1,201
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	1,035	1,035
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	135	135
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	696	696
78200300	PRISMATIC CURB REFLECTOR	EACH	24	24
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	696	696
* 88600100	DETECTOR LOOP, TYPE I	FOOT	775	775

* SPECIALTY ITEM