SUMMARY OF QUANTITITES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	MAINLINE, SIDEROAD 100% STATE 1000	PARKING LANES 100% STATE Y025
44200148	PAVEMENT PATCHING TYPE III, 12 INCH	SQ YD	16	16	
44200150	PAVEMENT PATCHING TYPE IV, 12 INCH	SQ YD	143	143	
44200176	PAVEMENT PATCHING TYPE I, 15 INCH	SQ YD	9	9	
44200180	PAVEMENT PATCHING TYPE II, 15 INCH	SQ YD	27	27	
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	4	4	
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	56	56	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	41	41	
50901760	PIPE HANDRAIL	FOOT	211	211	
60401810	GRATES, TYPE 3	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.0	4.5	0.5
67100100	MOBILIZATION	L SUM	1.0	0.9	0.1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0	1.0	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	1.0	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,800	1,800	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,556	1,556	

*-20RS-7, 21-6, 104RS, 105RS-4
**- 325, 42