

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK			URBAN	IL 29 100% STATE	IL 29 100% STATE SIDEWALK (CAMELOT TO SCHOOL)	IL 29 100% LOCAL E. MAIN ST.
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	1000-2A	SFTY-1B	1000-2A
20200100	EARTH EXCAVATION	CU YD	115.0	42.0	73.0	
20400800	FURNISHED EXCAVATION	CU YD	140.0		140.0	
25000200	SEEDING, CLASS 2	ACRE	0.6	0.2	0.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54.0	18.0	36.0	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54.0	18.0	36.0	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54.0	18.0	36.0	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.2	0.4	0.8	
25100125	MULCH, METHOD 3	ACRE	0.6	0.2	0.4	
28000500	INLET AND PIPE PROTECTION	EACH	4.0		4.0	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	170.0	170.0		
40600300	BITUMINOUS MATERIALS (PRIME COAT)	TON	85.3	84.3		1.0
40600300	AGGREGATE (PRIME COAT)	TON	447.0	444.0		3.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	519.0	489.0		30.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	2.0		
40600990	TEMPORARY RAMP	SQ YD	519.0	489.0		30.0
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4,335.0	4,335.0		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12,813.0	12,673.0		140.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	728.0	728.0		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	9,229.0	3,658.0	5,571.0	
42400800	DETECTABLE WARNINGS	SQ FT	76.2	35.8	40.4	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	167,379.0	165,759.0		1,620.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	33,783.0	33,783.0		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	22,388.0	22,388.0		
44000600	SIDEWALK REMOVAL	SQ FT	630.0	397.0	233.0	
44002000	CONCRETE CURB REMOVAL	FOOT	876.0	821.0	55.0	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	4,545.0	4,545.0		
44004250	PAVED SHOULDER REMOVAL	SQ YD	100.0		100.0	
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	50.0	50.0		
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	412.0	412.0		
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	32.0	32.0		
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	100.0	100.0		
44200537	CLASS A PATCHES, TYPE I, 9 INCH	SQ YD	50.0	50.0		
44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	132.0	132.0		
44200545	CLASS A PATCHES, TYPE III, 9 INCH	SQ YD	88.0	88.0		
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	100.0	100.0		

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pwork\PWIDOT\LAUGHLINR1\014037610572001-sht-500.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000 "/ IN.		CHECKED -	REVISED -
PLOT DATE = Mar-29-2010 10:12:17AM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
F.A.P. 75 (IL 29)			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	6(RS-8, TS), BRS-7	SANGAMON	111	3
CONTRACT NO. 72D01				
ILLINOIS FED. AID PROJECT				