MAINLINE RESURFACING SCHEDULE

STATION TO STATION	SIDE	DESCRIPTION	WIDTH	HMA SURFACE REMOVAL 2"	POLYMERIZED HMA SURFACE COURSE MIX "D", N70 2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HMA SURFACE	MATERIAL TRANSFER DEVICE
				SQ YD	TON				
ILL 336 (SBL)									
PE									
STA 240+00.0	LT	TURN LANE		426.4		0.16	0.9	47.8	
PE									
STA 256+00.0	LT	TURN LANE		426.6		0.16	0.9	47.8	
TR 147									
STA 294+38.0 TO 298+73.0	RT	TURN LANE		426.7		0.16	0.9	47.8	
STA 294+04.0 TO 299+94.0	LT	TURN LANE		586.9		0.22	1.2	65.7	
US 24 RAMP C									
STA 0+00.00 TO 23+95.33				4064.0	455.2	1.54	8.1		
ILL 61 RAMP D									
				5074.0	568.3	1.93	10.1		
CROSSOVERS									
BLOOMFIELD RD		CROSSOVER		626.4		0.24	1.3	70.2	
PE 186+00		CROSSOVER		216.9		0.08	0.4	24.3	
CH 28		CROSSOVER		626.9		0.24	1.3	70.2	
TR 205		CROSSOVER		1054.7		0.40	2.1	118.1	
TR 170		CROSSOVER		972.4		0.37	1.9	108.9	
PE 193+00		CROSSOVER		218.6		0.08	0.4	24.5	
PE 240+00		CROSSOVER		273.9		0.10	0.6	30.7	
PE 256+00		CROSSOVER		218.3		0.08	0.4	24.5	
TR 147		CROSSOVER		644.0		0.24	1.3	72.1	
SIDE ENTRANCES									
W. BLOOMFIELD RD		SIDE ENTRNC.		323.5		0.12	0.7	36.2	
E. BLOOMFIELD RD		SIDE ENTRNC.		324.3		0.12	0.7	36.3	
CH 28 RT		SIDE ENTRNC.		570.5		0.22	1.1	63.9	
E. TR 205		SIDE ENTRNC.		444.2		0.17	0.9	49.8	
W. TR 205		SIDE ENTRNC.		443.5		0.17	0.9	49.7	
E. TR 170		SIDE ENTRNC.		560.2		0.21	1.1	62.7	
W. TR 170		SIDE ENTRNC.		560.5		0.21	1.1	62.8	
E. TR 147		SIDE ENTRNC.		309.2		0.12	0.6	34.6	
W. TR 147		SIDE ENTRNC.		307.6		0.12	0.6	34.5	
TOTAL				220,423.5	24,687.4	83.8	440.8	2457.9	20308.8
USE				220,424	24,687	84	441	2458	20309

FILE NAME = c:\pw_work\PWIDOT\LAUGHLINRL\d0200120\D672D14_sht_schedule.dgn	USER NAME = laughlinrl	DESIGNED -	REVISED -
		DRAWN - STM	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - MTM	REVISED -
	PLOT DATE = Apr-09-2010 08:30:47AM	DATE - JANUARY 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 1"=50' | SHEET NO. 6 OF 14 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
302	1-7(RS)	ADAMS	38	9
		CONTRACT NO. 72D14		
	ILLINOIS	FED. AID PROJECT		