SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100 % STATE CONSTRUCTION TYPE CODE Y030-1E
67100100	MOBILIZATION	L SUM	1	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
81020400	CONDUIT PUSHED, 1 1/2" DIA., INTERMEDIATE METAL	FOOT	156	156
81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1463	1463
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1177	1177
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	9	9
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 30 AMP	EACH	1	1
83002600	LIGHT POLE, ALUMINUM, 40 FT. M. H., 15 FT. DAVIT ARM	EACH	9	9
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	9	9
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	36	36