

Bridge Repair Schedule

Pay Code	Item	Unit	Total			Urban	Urban	Urban	Rural	Rural	Rural	Rural	Rural	Rural
				Urban	Rural	SN 084-2000	SN 084-0014 SN 084-0015	SN 084-0016 SN 084-0017	SN 084-0018 SN 084-0019	SN 084-0020	SN 084-0022 SN 084-0023	SN 084-0088	SN 084-0100	SN 084-0101
20300100	CHANNEL EXCAVATION	CU YD	82.0	82.0	0.0	82.0								
28100105	STONE RIPRAP, CLASS A3	SQ YD	99.0	60.0	39.0			60.0		14.0		18.0	7.0	
28100205	STONE RIPRAP, CLASS A3	TON	46.0	30.0	16.0	30.0							8.0	8.0
28200200	FILTER FABRIC	SQ YD	99.0	60.0	39.0			60.0		14.0		18.0	7.0	
50102400	CONCRETE REMOVAL	CU YD	191.1	102.3	88.8		42.3	60.0	26.2	17.4	26.8	9.4	9.0	
50104650	SLOPE WALL REMOVAL	SQ YD	93.0	19.0	74.0			19.0			56.0		18.0	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	193.3	103.1	90.2		42.3	60.8	26.4	18.0	27.0	9.6	9.2	
50300300	PROTECTIVE COAT	SQ YD	549.7	282.4	267.3		101.5	180.9	68.5	46.5	75.0	25.3	52.0	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	22,980.0	11,770.0	11,210.0		5,020	6,750	3,140	1,730	3,840	1,240	1,260	
50800515	BAR SPLICERS	EACH	280.0	104.0	176.0		56	48	48	24	56	24	24	
51100100	SLOPE WALL 4"	SQ YD	37.0	19.0	18.0			19.0					18.0	
51100300	SLOPE WALL 6"	SQ YD	56.0	0.0	56.0						56.0			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	1,342.0	685.0	657.0		283.0	402.0	189.0	119.0	217.0	66.0	66.0	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	40.0	0.0	40.0									40.0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH = OR < 5 INCHES)	SQ FT	8.5	2.0	6.5		2.0		6.5					
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	14.0	0.0	14.0				1.0	11.0	2.0			
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	14.0	0.0	14.0				14.0					
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	122.0	0.0	122.0				48.0	34.0	40.0			
Z0065730	SLOPE WALL SLURRY PUMPING	CU YD	427.0	244.0	183.0		54.0	190.0		40.0	87.0	56.0		
	BRIDGE ABUTMENT DRAIN PIPE (6")	FOOT	78.0	78.0	0.0		78.0							