

I-55 - NORTH BOUND

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)	
555+20	PL	16	12	68		20			21.33			
550+60	DL	20	12	76	10	20				26.67	26.67	
547+50	PL	6	12	48		20	8.00					
547+50	DL	6	12	48		20	8.00					
546+00	PL	10	12	56		20	13.33					
546+00	DL	10	12	56		20	13.33					
545+80	PL	6	12	48		20	8.00					
545+80	DL	6	12	48		20	8.00					
545+50	PL	6	12	48		20	8.00					
545+50	DL	6	12	48		20	8.00					
518+50	DL	6	12	48		20	8.00					
518+30	DL	6	12	48		20	8.00					
517+95	DL	6	12	48		20	8.00					
510+00	DL	12	12	60		20			16.00			
508+40	DL	8	12	52		20	10.67					
507+40	PL	8	12	52		20	10.67					
507+40	DL	8	12	52		20	10.67					
URBAN Subtotal 3 =				904	10	340	0	131	37	27	27	
495+80	PL	6	12	48		20	8.00					
495+80	DL	6	12	48		20	8.00					
495+50	PL	6	12	48		20	8.00					
495+50	DL	6	12	48		20	8.00					
492+95	DL	6	12	48		20	8.00					
490+95	DL	9	12	54		20	12.00					
490+00	DL	6	12	48		20	8.00					
489+55	PL	6	12	48		20	8.00					
489+55	DL	6	12	48		20	8.00					
488+90	DL	8	12	52		20	10.67					
483+00	DL	6	12	48		20	8.00					
456+00	PL	6	12	48		20	8.00					
456+00	DL	6	12	48		20	8.00					
455+70	DL	6	12	48		20	8.00					
455+20	DL	10	12	56		20	13.33					
454+90	DL	28	12	92	14	20			37.33	37.33		
454+35	DL	33	12	102	17	20			44.00	44.00		
453+30	DL	10	12	56		20	13.33					
452+80	DL	12	12	60		20			16.00			
451+15	DL	12	12	60		20			16.00			
448+90	DL	6	12	48		20	8.00					
448+70	DL	12	12	60		20			16.00			
444+00	DL	6	12	48		20	8.00					
443+40	DL	10	12	56		20	13.33					
440+55	DL	12	12	60		20			16.00			
439+50	DL	12	12	60		20			16.00			
438+85	DL	6	12	48		20	8.00					
438+20	DL	6	12	48		20	8.00					
437+65	DL	6	12	48		20	8.00					
433+95	DL	12	12	60		20			16.00			
432+95	DL	16	12	68		20			21.33			
431+95	PL	6	12	48		20	8.00					
431+95	DL	6	12	48		20	8.00					
430+95	DL	6	12	48		20	8.00					
430+30	DL	6	12	48		20	8.00					
430+00	DL	6	12	48		20	8.00					
427+85	DL	8	12	52		20	10.67					
RURAL Subtotal 1 =				2,004	31	740	0	249	117	81	81	

I-55 - NORTH BOUND

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)	
427+65	PL	6	12	48		20		8.00				
427+65	DL	6	12	48		20		8.00				
427+50	DL	6	12	48		20		8.00				
426+00	DL	6	12	48		20		8.00				
424+10	DL	6	12	48		20		8.00				
423+50	DL	12	12	60		20			16.00			
423+10	DL	6	12	48		20		8.00				
422+85	DL	6	12	48		20		8.00				
422+60	DL	6	12	48		20		8.00				
418+90	DL	6	12	48		20		8.00				
418+25	DL	6	12	48		20		8.00				
418+00	DL	6	12	48		20		8.00				
417+20	DL	26	12	88	13	20				34.67	34.67	
416+70	DL	6	12	48		20		8.00				
414+00	DL	6	12	48		20		8.00				
411+00	PL	6	12	48		20		8.00				
411+00	DL	6	12	48		20		8.00				
401+75	DL	35	12	106	18	20				46.67	46.67	
400+40	DL	12	12	60		20			16.00			
399+85	DL	6	12	48		20		8.00				
399+50	DL	6	12	48		20		8.00				
398+60	DL	6	12	48		20		8.00				
398+35	DL	6	12	48		20		8.00				
398+00	DL	6	12	48		20		8.00				
397+00	DL	6	12	48		20		8.00				
396+25	DL	12	12	60		20			16.00			
395+05	DL	6	12	48		20		8.00				
390+05	DL	14	12	64		20			18.67			
389+30	DL	20	12	76	10	20				26.67	26.67	
388+90	DL	6	12	48		20		8.00				
387+80	DL	6	12	48		20		8.00				
387+00	DL	6	12	48		20		8.00				
386+00	DL	6	12	48		20		8.00				
385+75	DL	6	12	48		20		8.00				
378+25	DL	6	12	48		20		8.00				
375+00	PL	6	12	48		20		8.00				
374+75	PL	6	12	48		20		8.00				
374+75	DL	6	12	48		20		8.00				
374+60	PL	6	12	48		20		8.00				
374+00	DL	6	12	48		20		8.00				
365+85	PL	6	12	48		20		8.00				
356+20	PL	6	12	48		20		8.00				
336+25	DL	6	12	48		20		8.00				
335+90	DL	6	12	48		20		8.00				
335+75	DL	6	12	48		20		8.00				
335+55	DL	15	12	66		20			20.00			
335+15	DL	27	12	90	14	20				36.00	36.00	
334+85	DL	16	12	68		20			21.33			
334+65	DL	6	12	48		20		8.00				
334+40	DL	6	12	48		20		8.00				
333+70	DL	70	12	176	35	20				93.33	93.33	
333+20	DL	6	12	48		20		8.00				
332+80	DL	14	12	64		20			18.67			
332+25	DL	14	12	64		20			18.67			
RURAL Subtotal 2 =				3,010	90	1,080	0.00	328.00	145.33	237.33	237.33	

FILE NAME =
 et:\pwork\pwork\LAUGHLIN\laughlin1
 672043-sht-schedule2.dgn
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = Apr-29-2010 07:37:34AM

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	84-2(RS-3)	SANGAMON	156	14
CONTRACT NO. 72D43				
ILLINOIS FED. AID PROJECT				