

I-55 - SOUTH BOUND

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
448+00	DL	6	12	48		20		8.00			
449+15	DL	10	12	56		20		13.33			
450+80	DL	15	12	66		20			20.00		
473+00	DL	6	12	48		20		8.00			
478+00	DL	35	12	106	18	20				46.67	46.67
481+05	DL	25	12	86	13	20				33.33	33.33
484+40	DL	6	12	48		20		8.00			
485+05	DL	20	12	76	10	20				26.67	26.67
495+70	DL	6	12	48		20		8.00			
495+95	DL	6	12	48		20		8.00			
497+05	DL	8	12	52		20		10.67			
499+05	DL	10	12	56		20		13.33			
RURAL Subtotal 3 =				738	41	240	0	77	20	107	107
503+55	DL	8	12	52		20		10.67			
504+65	DL	12	12	60		20			16.00		
505+25	DL	6	12	48		20		8.00			
506+80	DL	8	12	52		20		10.67			
511+70	DL	35	12	106	18	20				46.67	46.67
513+50	PL	10	12	56		20		13.33			
513+50	DL	10	12	56		20		13.33			
526+00	DL	90	12	216	45	20				120.00	120.00
528+00	DL	6	12	48		20		8.00			
534+00	DL	10	12	56		20		13.33			
535+00	DL	6	12	48		20		8.00			
535+20	DL	6	12	48		20		8.00			
536+00	DL	8	12	52		20		10.67			
544+80	DL	35	12	106	18	20				46.67	46.67
545+80	DL	50	25	175		20				138.89	138.89
546+55	DL	6	12	48		20		8.00			
547+10	DL	25	12	86	13	20				33.33	33.33
548+40	PL	6	12	48		20		8.00			
548+40	DL	6	12	48		20		8.00			
551+70	PL	6	12	48		20		8.00			
551+70	DL	6	12	48		20		8.00			
554+70	DL	6	12	48		20		8.00			
557+20	DL	20	12	76	10	20				26.67	26.67
558+10	DL	80	12	196	40	20				106.67	106.67
558+80	DL	12	12	60		20			16.00		
559+50	DL	6	12	48		20		8.00			
560+00	DL	6	12	48		20		8.00			
561+00	DL	55	12	146	28	20				73.33	73.33
562+00	DL	6	12	48		20		8.00			
562+85	DL	70	12	176	35	20				93.33	93.33
563+60	DL	6	12	48		20		8.00			
564+85	DL	30	12	96	15	20				40.00	40.00
568+00	DL	10	12	56		20		13.33			
569+30	DL	125	12	286	63	20				166.67	166.67
574+80	DL	30	12	96	15	20				40.00	40.00
582+65	DL	12	12	60		20			16.00		
584+00	DL	8	12	52		20		10.67			
584+30	DL	6	12	48		20		8.00			
585+00	DL	30	12	96	15	20				40.00	40.00
585+60	DL	8	12	52		20		10.67			
585+80	DL	6	12	48		20		8.00			
587+75	DL	8	12	52		20		10.67			
URBAN Subtotal 1 =				3,341	315	840	0	245	48	972	972

I-55 - SOUTH BOUND

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
588+00	PL	6	12	48		20		8.00			
588+00	DL	6	12	48		20		8.00			
589+00	DL	80	12	196	40	20				106.67	106.67
598+95	DL	20	12	76	10	20				26.67	26.67
599+25	DL	6	12	48		20		8.00			
599+65	PL	6	12	48		20		8.00			
599+65	DL	6	12	48		20		8.00			
600+05	DL	6	12	48		20		8.00			
600+50	DL	6	12	48		20		8.00			
600+80	DL	6	12	48		20		8.00			
601+10	DL	10	12	56		20		13.33			
602+05	DL	210	12	456	105	20				280.00	280.00
603+95	DL	14	12	64		20			18.67		
604+70	DL	6	12	48		20		8.00			
605+00	PL	12	12	60		20			16.00		
605+00	DL	6	12	48		20		8.00			
605+50	DL	8	12	52		20		10.67			
606+00	DL	6	12	48		20		8.00			
612+00	PL	6	12	48		20		8.00			
612+00	DL	6	12	48		20		8.00			
612+50	PL	6	12	48		20		8.00			
612+50	DL	10	12	56		20		13.33			
612+80	DL	6	12	48		20		8.00			
616+00	DL	10	12	56		20		13.33			
617+00	DL	14	12	64		20			18.67		
617+45	DL	6	12	48		20		8.00			
618+40	DL	6	12	48		20		8.00			
623+00	DL	150	12	336	75	20				200.00	200.00
636+00	DL	70	12	176	35	20				93.33	93.33
652+60	DL	20	12	76	10	20				26.67	26.67
659+00	PL	20	12	76	10	20				26.67	26.67
659+00	DL	30	12	96	15	20				40.00	40.00
660+00	DL	14	12	64		20			18.67		
660+35	DL	6	12	48		20		8.00			
661+00	DL	30	12	96	15	20				40.00	40.00
661+55	DL	12	12	60		20			16.00		
671+00	DL	12	12	60		20			16.00		
671+50	DL	6	12	48		20		8.00			
673+00	DL	12	12	60		20			16.00		
676+20	PL	8	12	52		20		10.67			
676+20	DL	8	12	52		20		10.67			
680+00	DL	6	12	48		20		8.00			
681+00	DL	10	12	56		20		13.33			
681+50	DL	10	12	56		20		13.33			
688+40	DL	15	12	66		20			20.00		
689+80	DL	42	12	120	21	20				56.00	56.00
690+90	PL	6	12	48		20		8.00			
690+90	DL	12	12	60		20			16.00		
691+80	DL	12	12	60		20			16.00		
URBAN Subtotal 2 =				3,766	336	980	0	267	172	896	896

FILE NAME =
 et:\pw\work\PIWIDOT\LAUGHLINRL\0176540\0672043-sht-schedule2.dgn
 USER NAME = laughlinr1
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = Apr-29-2010 07:37:42AM

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	84-2(RS-3)	SANGAMON	156	17
CONTRACT NO. 72D43				
ILLINOIS FED. AID PROJECT				