

BUTT JOINT SCHEDULE

LOCATION	HMA SURF REMOVAL BUTT JOINT (sq yd)	TEMP RAMPS (SQ YD)
Sta 285+00 to Sta 285+10 NB	40.0	20.0
Sta 285+00 to Sta 285+10 SB	40.0	20.0
Sta 290+08 to Sta 290+18 SB (SN 084-0023)	40.0	20.0
Sta 290+62 to Sta 290+72 NB (SN 084-0022)	40.0	20.0
Sta 291+68 to Sta 291+78 SB (SN 084-0023)	40.0	20.0
Sta 292+22 to Sta 292+32 NB (SN 084-0022)	40.0	20.0
Sta 330+55 to Sta 330+65 SB (Sherman Exit)	17.8	8.9
Sta 336+00 to Sta 336+10 NB (Sherman Exit)	17.8	8.9
Sta 339+00 to Sta 339+10 SB (On-ramp)	17.8	8.9
Sta 344+66 to Sta 344+76 NB (SN 084-0020)	40.0	20.0
Sta 345+40 to Sta 345+50 SB (SN 084-0021)	40.0	20.0
Sta 348+37 to Sta 348+47 NB (SN 084-0020)	40.0	20.0
Sta 349+10 to Sta 349+20 SB (SN 084-0021)	40.0	20.0
Sta 398+95 to Sta 399+05 SB (Rest Area)	17.8	8.9
Sta 411+95 to Sta 412+05 SB (Rest Area)	17.8	8.9
Sta 456+53 to Sta 456+63 SB (SN 084-0019)	26.7	13.3
Sta 456+53 to Sta 456+63 NB (SN 084-0018)	26.7	13.3
Sta 467+87 to Sta 467+97 SB (SN 084-0019)	26.7	13.3
Sta 467+87 to Sta 467+97 NB (SN 084-0018)	26.7	13.3
Sta 482+20 to Sta 482+30 NB (Rest Area)	17.8	8.9
Sta 494+50 to Sta 494+60 NB (Rest Area)	17.8	8.9
Sta 591+71 to Sta 591+81 NB (SN 084-0017)	26.7	13.3
Sta 592+42 to Sta 592+52 SB (SN 084-0016)	26.7	13.3
Sta 594+50 to Sta 594+60 NB (SN 084-0017)	26.7	13.3
Sta 595+56 to Sta 595+66 SB (SN 084-0016)	26.7	13.3
Sta 607+59 to Sta 607+69 SB (SN 084-0014)	26.7	13.3
Sta 607+59 to Sta 607+69 NB (SN 084-0015)	26.7	13.3
Sta 610+69 to Sta 610+79 SB (SN 084-0014)	26.7	13.3
Sta 610+70 to Sta 610+80 NB (SN 084-0015)	26.7	13.3
Sta 695+65 to Sta 695+75 SB	26.7	13.3
Sta 695+65 to Sta 695+75 NB	26.7	13.3
URBAN TOTAL	267	133
RURAL TOTAL	631	316

Short Term Pavement Marking

Location	Urban/ Rural	Center Line White Foot	Shoulder Yellow Foot	Shoulder White Foot	Total Foot	Wrk Zone Mkg Rem Sq Ft	
I-55 Northbound							
Sta 285+00 to 502+00	R	2,170	1,736	1,736	5,642	579	
Shreman Ramp C	R		123	123	246	41	
Sta 502+00 to 695+65	U	1,937	1,550	1,550	5,037	517	
Sangamon Ave Ramp 5	U		120	120	240	40	
Sangamon Ave Ramp 6	U		112	112	224	38	
Sangamon Ave Ramp 7	U		112	112	224	38	
Sangamon Ave Ramp 8	U		72	72	144	24	
I-55 Southbound							
Sta 285+00 to 423+70	R	2,954	1,182	1,182	5,318	394	
Sta 432+70 to 502+00	R	693	555	555	1,803	12	
Sherman Ramp A	R		200	200	400	67	
Sherman Ramp B	R		160	160	320	54	
Sta 502+00 to 695+65	U	1,937	1,550	1,550	5,037	517	
Sangamon Ave Ramp 1	U		112	112	224	38	
Sangamon Ave Ramp 2	U		96	96	192	32	
Sangamon Ave Ramp 3	U		112	112	224	38	
Sangamon Ave Ramp 4	U		72	72	144	24	
Sang. Ave. Sta 16+00 to 65+25 EB	U	493	394	394	1,281	132	
Camp Butler Sta 65+25 to 80+00 EB	U	148	118	118	384	40	
Sang. Ave. Sta 16+00 to 65+25 WB	U	493	394	394	1,281	132	
Camp Butler Sta 65+25 to 80+00 WB	U	148	118	118	384	40	
Br Stage Const (0018 & 0019)	R					24,500	
Br Stage Const (0014, 15 & 0016, 17)	U					22,800	
Br Stage Const (0022, 23)	R					16,700	
Br Stage Const (0021)	R					8,000	
					Urban Total	15,020	24,450
					Rural Total	13,729	50,347
					Total	28,749	74,797