

Guardrail Schedule

LOCATION	REMOVE EXIST GUARDRAIL ( FT )	SPBGR TY A ( FT )	TRAF BAR TERM TY 1 SPL ( EACH )	TRAF BAR TERM TY 2 ( EACH )	TRAF BAR TERM TY 6 ( EACH )	TERM MARKER DA ( EACH )	GUARDRAIL REFLECTORS ( EACH )
I-55 - SBL							
510+30 TO 510+80 ( OUT )			1			1	
510+80 TO 512+80 ( OUT )		200					4
512+30 TO 512+80 ( OUT )	50						
SN 084-0016 ( MED - Appr )		200	1		1	1	4
SN 084-0016 ( MED - Depart )		212.5		1	1		4
SN 084-0014 ( MED - Appr )		187.5	1		1	1	4
I-55 - NBL							
SN 084-0017 ( MED - Appr )		250	1		1	1	5
SN 084-0015 ( MED - Appr )		187.5	1		1	1	4
SANGAMON AVE - EBL							
41+25 TO 41+75 ( OUT )	50		1			1	
41+25 TO 41+75 ( MED )	50		1			1	
54+14 TO 54+64 ( MED )			1			1	
54+64 TO 55+64 ( MED )		100					3
55+64 TO 55+76.5 ( MED )				1			
SANGAMON AVE - WBL							
44+26 TO 44+76 ( MED )	50		1			1	
56+17.5 TO 56+30 ( MED )				1			
56+30 TO 57+30 ( MED )		100					3
57+30 TO 57+80 ( MED )			1			1	
URBAN TOTA	200	1437.5	10	3	5	10	31

SIGNING SCHEDULE

PAY CODE	DESCRIPTION	UNIT	TOTAL
72000100	SIGN PANEL - TYPE 1	SQ FT	22
72100100	SIGN PANEL OVERLAY	SQ FT	6
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	9
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	45
X0325220	REMOVE AND REINSTALL SIGN PANEL	SQ FT	81