

GUARDRAIL SCHEDULE

LOCATION	STATION TO STATION		SIDE	63100167	63100169	63100075	X0325194	6E+07	6E+07	63200310	78201000	78200410	20200100	20200200
				TRAF. BARR. TERM TY 1 SPC. (TANGENT)	TRAF. BARR. TERM TY 1 SPC. (FLARED)	TRAF. BARR. TERM. TY 5A	IMPACT ATTN. (FULLY REDIRECTIVE, NARROW) TL3, SPC	SPBGR, 6' POSTS	SPBGR, 9' POSTS	GUARDRAIL REMOVAL	TERMINAL MARKERS- DIRECT APPLIED	GUARDRAIL MARKERS	EARTH EXCAVATION	ROCK EXCAVATION
LOC #12	733+25	757+98	RT											
	733+25	733+75	RT	1						2473.00				
	733+75	757+50	RT					2375.00			1	30		
	757+50	768+00	RT	1							1			
LOCATION #12 SUB-TOTALS				2				2375.00		2473.00	2	30		
LOC #14	778+28	794+82	RT							1654.00				
	778+19.50	778+69.50	RT	1							1			
	778+69.50	794+32	RT					1592.50				20		
	794+32	794+82	RT	1							1			
LOCATION #14 SUB-TOTALS				2				1592.50		1654.00	2	20		
LOC #16	840+50	844+46	RT							398.00				
	840+46	840+66	RT	1							1			
	840+66	843+96	RT					400.00				5		
	843+96	844+46	RT	1							1			
LOCATION #16 SUB-TOTALS				2				400.00		398.00	2	5		
LOC #17	843+28	844+40	RT							112.00				
	843+28	843+78	RT	1							1			
	843+78	844+15.50	RT					37.50				1		
	844+15.50	844+65.50	RT	1							1			
LOCATION #17 SUB-TOTALS				2				37.50		112.00	2	1		
JOB TOTAL				24	1	3	1	2387.50	5437.50	8595.00	25	110	60	30
				EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH

FILE NAME *	USER NAME * laughlinr1	DESIGNED -	REVISED -
c:\pvc\work\PHIDOT\LAUGHLINR1\08183217.D	72059-sht-schedule.dgn	DRAWN -	REVISED -
	PLOT SCALE = 120.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Mar-19-2010 11:34:47AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
510	120 GUARDRAIL-1	HANCOCK	7	5
			CONTRACT NO. 72059	
ILLINOIS FED. AID PROJECT				