

PCC SIDEWALK, 4"

| LOCATION | AREA (SQ FT) |
|--------------|--------------|
| NW Quad | 56.5 |
| NW Quad | 36.6 |
| NE Quad | 73.2 |
| SW Quad | 85.4 |
| SE Quad | 253.6 |
| SE Island | 30.4 |
| East Median | 35.2 |
| West Median | 31.9 |
| North Median | 29.0 |
| TOTAL | 631.8 |

DETECTABLE WARNINGS

| LOCATION | LENGTH | WIDTH | AREA (SQ FT) |
|--------------|--------|-------|--------------|
| NW Quad | 2.0 | 5 | 10.0 |
| NW Quad | 2.0 | 5 | 10.0 |
| NE Quad | 2.0 | 9.3 | 18.6 |
| SW Quad | 2.0 | 7.2 | 14.4 |
| SE Quad | 2 | 5 | 10.0 |
| SE Island | 2.0 | 5 | 10.0 |
| SE Island | 2.0 | 5.6 | 11.2 |
| West Median | 5.4 | 5 | 27.0 |
| East Median | 2 | 5 | 10.0 |
| East Median | 2 | 5 | 10.0 |
| North Median | 3.7 | 5 | 18.5 |
| TOTAL | | | 149.7 |

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 12"

| LOCATION | LENGTH (FOOT) |
|--------------------------|---------------|
| IL 29 | |
| STA 833+03 TO STA 833+09 | NW Quad 5.2 |
| POPLAR | |
| STA 49+62 TO STA 49+68 | NW Quad 6.8 |
| STA 49+72 TO STA 49+75 | NW Quad 5.0 |
| STA 49+65 TO STA 49+74 | NE Quad 12.7 |
| STA 50+37 TO STA 50+46 | SW Quad 12.5 |
| STA 50+42 TO STA 50+46 | SE Quad 6.0 |
| STA 50+62 TO STA 50+69 | SE Quad 7.6 |
| TOTAL | 55.8 |

PCC BASE COURSE, 12"

| LOCATION | AREA (SY) |
|--------------------------|-----------------|
| STA 833+03 TO STA 833+08 | West Median 1.1 |
| STA 833+79 TO STA 833+84 | SE Island 1.2 |
| STA 833+81 TO STA 833+85 | SE Island 0.3 |
| TOTAL | 2.6 |

EARTH EXCAVATION

| LOCATION | AREA (SQ FT) | VOLUME (CU YD) |
|--------------|--------------|----------------|
| NW Quad | 56.5 | 0.7 |
| NW Quad | 36.6 | 0.5 |
| NE Quad | 22.1 | 0.3 |
| SW Quad | 41.6 | 0.5 |
| SE Quad | 253.6 | 3.1 |
| TOTAL | | 5.1 |

COMBINATION CURB & GUTTER REMOVAL

| LOCATION | LENGTH (FOOT) |
|--------------------------|---------------|
| IL 29 | |
| STA 833+03 TO STA 833+09 | NW Quad 5.2 |
| STA 833+80 TO STA 833+85 | SE Island 5.2 |
| POPLAR | |
| STA 49+62 TO STA 49+68 | NW Quad 6.8 |
| STA 49+72 TO STA 49+75 | NW Quad 5.0 |
| STA 49+65 TO STA 49+74 | NE Quad 12.7 |
| STA 50+37 TO STA 50+46 | SW Quad 12.5 |
| STA 50+26 TO STA 50+29 | SE Island 5.0 |
| STA 50+42 TO STA 50+46 | SE Quad 6.0 |
| STA 50+62 TO STA 50+69 | SE Quad 7.6 |
| TOTAL | 66.0 |

SIDEWALK REMOVAL

| LOCATION | AVG LENGTH | WIDTH | AREA (SQ FT) |
|--------------------------|--------------|-------|--------------|
| POPLAR | | | |
| STA 50+40 TO STA 50+56 | SW Quad 12.7 | 4 | 50.8 |
| IL 29 | | | |
| STA 833+80 TO STA 833+96 | NE Quad 12.7 | 4 | 50.8 |
| TOTAL | | | 101.6 |

MEDIAN REMOVAL

| LOCATION | AREA (SQ FT) |
|--------------------------|---------------------|
| POPLAR | |
| STA 49+63 TO STA 49+69 | North Median 34.0 |
| IL 29 | |
| STA 833+04 TO STA 833+09 | West Median 34.4 |
| STA 833+85 TO STA 833+90 | East Median 40.3 |
| STA 833+80 TO STA 833+85 | SE Quad Island 43.3 |
| TOTAL | 152.0 |

RELOCATE SIGN PANEL

| EXISTING LOCATION | PROPOSED LOCATION | AREA (SQ FT) |
|-------------------|-------------------|--------------|
| STA 49+64 RT | STA 49+58 RT | 5.2 |
| STA 49+66 LT | STA 49+61 LT | 5.2 |
| TOTAL | | 10.4 |

PAINT PAVEMENT MARKING- LINE 24"

| LOCATION | DIRECTION | DESCRIPTION | LENGTH (FOOT) |
|--------------|------------|-------------|---------------|
| POPLAR | | | |
| 49+57 | SB | STOP BAR | 17.3 |
| 50+27 | NB | STOP BAR | 20.0 |
| 50+33 | TURN LN EB | STOP BAR | 22.2 |
| IL 29 | | | |
| 833+00 | WB | RR STOP BAR | 18.6 |
| TOTAL | | | 78.1 |

PAINT PAVEMENT MARKING- LINE 6"

| LOCATION | COLOR | DIRECTION | DESCRIPTION | LENGTH (FOOT) |
|--------------|-------|------------|-------------|---------------|
| POPLAR | | | | |
| 49+69 | WHITE | SBL | CROSSWALK | 47.2 |
| 49+69 | WHITE | NBL | CROSSWALK | 52.1 |
| IL 29 | | | | |
| 833+09 | WHITE | EB | CROSSWALK | 71.1 |
| 833+09 | WHITE | WB | CROSSWALK | 40.2 |
| 833+84 | WHITE | EB | CROSSWALK | 36.0 |
| 833+84 | WHITE | WB | CROSSWALK | 43.8 |
| 833+81 | WHITE | TURN LN EB | CROSSWALK | 43.2 |
| TOTAL | | | | 333.6 |

WORK ZONE PAVEMENT MARKING REMOVAL

| LOCATION | LENGTH | WIDTH | AREA (SQ FT) |
|--------------|---------------------|-------|--------------|
| STOP BARS | | | |
| STA 49+63 | North Stop Bar 20.1 | 2 | 40.2 |
| STA 50+34 | SE Stop Bar 21.9 | 2 | 43.8 |
| STA 833+05 | West Stop Bar 19.1 | 2 | 38.2 |
| EDGE LINES | | | |
| North Median | 12.4 | 0.4 | 5.0 |
| West Median | 12.2 | 0.4 | 4.9 |
| East Median | 12.4 | 0.4 | 5.0 |
| SE Island | 15 | 0.4 | 6.0 |
| TOTAL | | | 143.0 |