

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

80/20 FED/ST

FAP 750

FAS 719

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80/20 FED/ST		80/20 FED/ST	
				FAP 750	FAS 719	ROADWAY SECTION 114B-1(1) I000	STRUCTURE SN. 026-2020 Y007
* 542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	48				
54215550	METAL END SECTIONS 15"	EACH	3	33		15	
				2		1	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	8			8	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	60			60	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1			1	
60255500	MANHOLES TO BE ADJUSTED	EACH	3			3	
60260100	INLETS TO BE ADJUSTED	EACH	2			2	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6			6	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	374			374	
** 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	300	300			
** * 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4			
** * 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
** 63200310	GUARDRAIL REMOVAL	FOOT	314	314			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	4		4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3		3	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1		1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5		0.5	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5		0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5		0.5	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5		0.5	

\* SEE SPECIAL PROVISIONS

\*\* SPECIALTY ITEM

FILE NAME =	USER NAME = IE Consultants	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Gr\58826-5\CADD Sheets\0774118-sht-500.dgn	DRAWN -	REVISED -	•			114B-1(1) & 114B-1(2)	FAYETTE	54	6	
PLOT SCALE = 10.0000' / IN.	CHECKED -	REVISED -	• F.A.P. RTE. 750, F.A.S. RTE. 719			CONTRACT NO. 74110				
PLOT DATE = 9/29/2009	DATE -	REVISED -	FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.			