

## RESURFACING SCHEDULE

STATION TO STATION		LENGTH	AVERAGE PAVEMENT WIDTH	AREA		HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	PAVED SHOULDER REMOVAL	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
		FOOT	FOOT	SQ FT	SQ YD	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	UNIT	TON	SQ YD	SQ YD	
1889+18.00 TO 1889+53.00		35.0	30.0	1050.0	14.4	0.0	11.7	0.2	9.8	2.1	15.6	0.0	0.7	2.3	86.7	14.4	
1889+53.00 TO 1897+10.00		757.0	30.0	22710.0	2186.9	0.0	252.3	5.0	212.0	91.8	336.4	0.0	15.1	43.3	0.0	0.0	
1897+10.00 BK= 1202+24.00 A		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
1202+24.00 TO 1219+01.80		1677.8	30.0	50334.0	4847.0	0.0	559.3	11.2	469.8	203.6	745.7	0.0	33.6	95.3	0.0	0.0	
1219+01.80 BK= 1219+02.00 A		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
1219+02.00 TO 1310+50.00		9148.0	30.0	274440.0	26427.6	0.0	3049.3	61.0	2561.4	1110.0	4065.8	0.0	183.0	547.9	0.0	0.0	
1310+50.00 TO 1310+85.00		35.0	30.0	1050.0	0.0	101.1	11.7	0.2	9.8	4.2	15.6	0.0	0.7	2.3	0.0	0.0	
1310+85.00 TO 1318+75.00		790.0	27.0	21330.0	0.0	2106.7	237.0	4.7	199.1	88.5	263.3	87.8	7.9	22.1	0.0	0.0	
1318+75.00 TO 1318+95.00		20.0	31.0	620.0	0.0	53.3	6.9	0.1	5.8	2.6	6.7	2.2	0.2	0.7	0.0	0.0	
1318+95.00 TO 1319+10.00		15.0	32.0	480.0	0.0	40.0	5.3	0.1	4.5	2.2	0.0	1.7	0.2	1.0	0.0	0.0	
1319+10.00 TO 1320+41.00		131.0	32.0	4192.0	465.8	0.0	46.6	0.9	39.1	19.6	0.0	14.6	0.0	6.7	0.0	17.8	
1320+41.00 TO 1322+26.00		185.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
1322+26.00 TO 1323+61.00		135.0	32.0	4320.0	480.0	0.0	48.0	1.0	40.3	20.2	0.0	15.0	0.0	9.0	0.0	17.8	
1323+61.00 TO 1323+91.00		30.0	31.0	930.0	93.3	0.0	10.3	0.2	8.7	3.9	10.0	3.3	0.3	2.0	0.0	0.0	
1323+91.00 TO 1324+26.00		35.0	27.0	945.0	0.0	93.3	10.5	0.2	8.8	3.9	11.7	3.9	0.4	2.3	0.0	0.0	
1324+26.00 TO 1330+05.00		579.0	27.0	15633.0	0.0	1544.0	173.7	3.5	145.9	64.8	193.0	64.3	5.8	15.5	0.0	0.0	
1330+05.00 TO 1330+40.00		35.0	30.0	1050.0	0.0	93.3	11.7	0.2	9.8	3.9	23.3	7.8	0.7	2.3	0.0	0.0	
1330+40.00 TO 1333+50.00		310.0	30.0	9300.0	826.7	0.0	103.3	2.1	86.8	34.7	206.7	68.9	6.2	17.0	0.0	0.0	
1333+50.00 TO 1333+85.00		35.0	32.0	1120.0	17.8	0.0	12.4	0.2	10.5	2.6	0.0	0.0	0.0	2.3	106.7	17.8	
1333+85.00 TO 1337+15.00		330.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
1337+15.00 TO 1337+50.00		35.0	32.0	1120.0	17.8	0.0	12.4	0.2	10.5	2.6	0.0	0.0	0.0	2.3	106.7	17.8	
1337+50.00 TO 1342+00.00		450.0	32.0	14400.0	1600.0	0.0	160.0	3.2	134.4	67.2	0.0	0.0	0.0	29.9	8.0	0.0	
1342+00.00 TO 1342+35.00		35.0	32.0	1120.0	17.8	0.0	12.4	0.2	10.5	2.6	0.0	0.0	0.0	2.3	106.7	17.8	
1342+35.00 TO 1345+65.00		330.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
1345+65.00 TO 1346+00.00		35.0	32.0	1120.0	17.8	0.0	12.4	0.2	10.5	2.6	0.0	0.0	0.0	2.3	106.7	17.8	
1346+00.00 TO 1359+15.00		1315.0	30.0	39450.0	3506.7	0.0	438.3	8.8	368.2	147.3	876.7	292.2	26.3	87.4	0.0	0.0	
1359+15.00 TO 1359+50.00		35.0	30.0	1050.0	0.0	93.3	11.7	0.2	9.8	3.9	23.3	7.8	0.7	2.3	0.0	0.0	
1359+50.00 TO 1365+90.00		640.0	24.0	15360.0	0.0	1706.7	170.7	3.4	143.4	71.7	0.0	0.0	0.0	0.0	0.0	0.0	
1365+90.00 TO 1366+25.00		35.0	30.0	1050.0	0.0	101.1	11.7	0.2	9.8	4.2	15.6	0.0	0.7	2.3	0.0	0.0	
1366+25.00 TO 1366+28.00		3.0	30.0	90.0	8.7	0.0	1.0	0.0	0.8	0.4	1.3	0.0	0.1	0.2	0.0	0.0	
1366+28.00 BK= 1366+00.00 A		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
1366+00.00 TO 1373+00.00		700.0	30.0	21000.0	2022.2	0.0	233.3	4.7	196.0	84.9	311.1	0.0	14.0	40.8	0.0	0.0	
1373+00.00 TO 1377+03.00		403.0	30.0	12090.0	1164.2	0.0	134.3	2.7	112.8	48.9	179.1	0.0	8.1	18.6	0.0	0.0	
1377+03.00 TO 1377+38.00		35.0	30.0	1050.0	0.0	101.1	11.7	0.2	9.8	4.2	15.6	0.0	0.7	2.3	0.0	0.0	
1377+38.00 TO 1381+30.00		392.0	24.0	9408.0	0.0	1045.3	104.5	2.1	87.8	43.9	0.0	0.0	0.0	0.0	0.0	0.0	

FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pv_work\PW\DOT\SWARTZRW\dms54414\sh	sch_74317.dgn	DRAWN -	REVISED -		SCALE: NA	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	2796	(L,K)RS-2	EFFINGHAM	58	13
	PLOT SCALE = 28.0000' / IN.	CHECKED -	REVISED -		CONTRACT NO. 74317								
	PLOT DATE = 3/17/2018	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								