

PAVEMENT MARKING SCHEDULE	LENGTH	PAINT PAVEMENT MARKING - LINE 4" WHITE	PAINT PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	EACH
1889+18.00 TO 1897+10.00	792.0	1584.0	1584.0	0.0	0.0	0.0	0.0	0.0	0.0	3168.0	0.0	0.0	0.0	320.0	26.7	10.0
1897+10.00 BK= 1202+24.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1202+24.00 TO 1219+01.80	1677.8	3255.6	3355.6	0.0	0.0	0.0	0.0	0.0	0.0	6611.2	0.0	0.0	0.0	672.0	56.0	21.0
1219+01.80 BK= 1219+02.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1219+02.00 TO 1229+95.00	1093.0	2134.0	2186.0	0.0	0.0	0.0	0.0	0.0	0.0	4320.0	0.0	0.0	0.0	432.0	36.0	14.0
1229+95.00 TO 1241+00.00	1105.0	2210.0	1381.3	0.0	0.0	0.0	0.0	0.0	0.0	3591.3	0.0	0.0	0.0	448.0	37.3	14.0
1241+00.00 TO 1264+10.00	2310.0	4503.0	577.5	0.0	0.0	0.0	0.0	0.0	0.0	5080.5	0.0	0.0	0.0	928.0	77.3	29.0
1264+10.00 TO 1276+16.00	1206.0	2236.0	1507.5	0.0	0.0	0.0	0.0	0.0	0.0	3743.5	0.0	0.0	0.0	480.0	40.0	15.0
1276+16.00 TO 1323+31.00	4715.0	9214.0	9430.0	0.0	0.0	0.0	0.0	0.0	0.0	18644.0	0.0	0.0	0.0	1888.0	157.3	78.0
1323+31.00 TO 1332+07.00	876.0	1669.0	1095.0	0.0	0.0	0.0	0.0	0.0	0.0	2764.0	0.0	0.0	0.0	352.0	29.3	22.0
1332+07.00 TO 1355+23.00	2316.0	4632.0	579.0	0.0	0.0	0.0	0.0	0.0	0.0	5211.0	0.0	0.0	0.0	928.0	77.3	29.0
1355+23.00 TO 1365+80.00	1057.0	2114.0	1321.3	0.0	0.0	0.0	0.0	0.0	0.0	3435.3	0.0	0.0	0.0	416.0	34.7	13.0
1365+80.00 TO 1366+28.00	48.0	96.0	96.0	0.0	0.0	0.0	0.0	0.0	0.0	192.0	0.0	0.0	0.0	16.0	1.3	1.0
1366+28.00 BK= 1366+00.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1366+00.00 TO 1373+00.00	700.0	1400.0	1400.0	0.0	0.0	0.0	0.0	0.0	0.0	2800.0	0.0	0.0	0.0	288.0	24.0	9.0
1373+00.00 TO 1386+00.00	1300.0	2600.0	2600.0	0.0	0.0	0.0	0.0	0.0	0.0	5200.0	0.0	0.0	0.0	528.0	44.0	16.0
1386+00.00 TO 1386+50.00	50.0	100.0	12.5	0.0	0.0	0.0	0.0	0.0	0.0	112.5	0.0	0.0	0.0	16.0	1.3	1.0
1386+50.00 TO 1399+75.00	1325.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	69.0
1399+75.00 TO 1408+40.00	865.0	0.0	0.0	1730.0	1081.3	0.0	0.0	0.0	0.0	2811.3	0.0	0.0	0.0	352.0	29.3	11.0
1408+40.00 TO 1410+15.00	175.0	0.0	0.0	350.0	43.8	0.0	0.0	0.0	0.0	393.8	0.0	0.0	0.0	64.0	5.3	2.0
1410+15.00 TO 1414+77.00	462.0	0.0	0.0	924.0	577.5	0.0	0.0	0.0	0.0	1501.5	0.0	0.0	0.0	192.0	16.0	6.0
1414+77.00 TO 1415+57.00	80.0	0.0	0.0	160.0	160.0	0.0	0.0	0.0	0.0	320.0	0.0	0.0	0.0	32.0	2.7	6.0
1415+57.00 TO 1422+73.00	716.0	0.0	0.0	1432.0	1432.0	0.0	181.5	0.0	0.0	2864.0	0.0	181.5	0.0	576.0	48.0	40.0
1422+73.00 TO 1423+05.00	32.0	0.0	0.0	64.0	64.0	0.0	0.0	0.0	0.0	128.0	0.0	0.0	0.0	32.0	2.7	0.0
1423+05.00 TO 1424+30.00	125.0	0.0	0.0	250.0	250.0	125.0	0.0	0.0	0.0	500.0	125.0	0.0	0.0	96.0	8.0	9.0
1424+30.00 TO 1425+70.00	140.0	0.0	0.0	280.0	0.0	0.0	0.0	31.2	0.0	280.0	0.0	0.0	31.2	0.0	0.0	2.0
1425+70.00 TO 1431+60.00	590.0	0.0	0.0	1180.0	1180.0	0.0	155.1	0.0	0.0	2360.0	0.0	155.1	0.0	480.0	40.0	30.0
1431+60.00 TO 1432+40.00	80.0	0.0	0.0	160.0	160.0	0.0	0.0	0.0	0.0	320.0	0.0	0.0	0.0	32.0	2.7	6.0
1432+40.00 TO 1436+36.00	396.0	0.0	0.0	792.0	495.0	0.0	0.0	0.0	0.0	1287.0	0.0	0.0	0.0	160.0	13.3	5.0
1436+36.00 TO 1438+95.00	259.0	0.0	0.0	518.0	64.8	0.0	0.0	0.0	0.0	582.8	0.0	0.0	0.0	96.0	8.0	3.0
1438+95.00 TO 1443+51.00	456.0	0.0	0.0	912.0	570.0	0.0	0.0	0.0	0.0	1482.0	0.0	0.0	0.0	176.0	14.7	6.0
1443+51.00 TO 1450+65.00	714.0	0.0	0.0	1428.0	1428.0	0.0	257.2	0.0	0.0	2856.0	0.0	257.2	0.0	288.0	24.0	36.0
TOTALS		37748.0	27126.0	10180.0	7506.0	125.0	594.0	31.0	82559.0	125.0	594.0	31.0	10288.0	857.0	503.0	