



Distance from C7  
to Controller = +/-1365'

NOTE: ALL DELINEATOR POST WITH  
CHEVRONS IN CIRCUIT "C" (7 TOTAL)  
ARE EXISTING.

7 Delineators in  
Circuit "C"

**BILL OF MATERIALS FOR "C" ILLUMINATED DELINEATORS  
(FAR EAST CURVE-NORTH OF HIGHWAY)**

CONDUIT IN TRENCH, 2" DIA., PVC	1072.0	FOOT
CONDUIT, AUGERED, 2" DIA., PVC	40.0	FOOT
CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., GALVANIZED STEEL	28.0	FOOT
CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	185.0	FOOT
GULFBOX JUNCTION	2.0	EACH
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO 8	2928.0	FOOT
ILLUMINATED DELINEATOR SYSTEM	0.3	L SUM

FILE NAME = c:\pw\work\PWIDOT\SWARTZRW\dms54414\07	USER NAME = swartzrw 4317-shr-Geometrics.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ILLUMINATED DELINEATOR SYSTEM CIRCUIT "C" PLAN LAYOUT</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 40,0000' / IN.	CHECKED -	REVISED -			2796	IL,KRS-2	EFFINGHAM	58	44	
	PLOT DATE = 3/17/2010	DATE -	REVISED -			SCALE: 1"=40'		SHEET NO. 4 OF 4 SHEETS		STA. 1320+00 TO STA. 1332+50	
						CONTRACT NO. 74317 ILLINOIS FED. AID PROJECT					