EX. JUNCTION BOX
NOT TO BE DISTURBED

EX. STORM SEWERS NOT
TO BE DISTURBED

℄ RAMP F

91°51'15"

℄ RAMP H

EXISTING GUARDRAIL
TO BE REMOVED

NOTE:

CONTRACTOR TO PROVIDE FINAL GRADING AROUND THE PROPOSED PIER, SLOPEWALLS, AND ATTENUATOR PADS TO MAINTAIN EXISTING DRAINAGE PATTERNS. COST INCLUDED IN COST OF PROJECT.

150+00 | 155+00 | 160+00

℄ INTERSTATE 72

REGRADE MEDIAN AS
NECESSARY TO DRAIN
(COST INCLUDED IN THE COST
OF VARIOUS ITEMS OF WORK)

REPLACE EXISTING ATTENUATORS
(2 LOCATIONS) SEE MISC. DETAILS
AND SPECIAL PROVISIONS.

REMOVE AND RECONSTRUCT ATTENUATOR
PADS (2 LOCATIONS) SEE MISC. DETAILS

EXISTING GUARDRAIL
TO BE REMOVED

STA. 152+94.64 1-72 =
STA. 1154+77.78 US 51

℄ RAMP B

℄ RAMP D

EXISTING
6' X 6' BOX CULVERT
NOT TO BE DISTURBED

℄ US 51

N

0' 50' 100'

SCALE 1" = 50'

PLAN
STAMPED
PLOTTED
ALIGNMENT CHECKED
PROFILE CHECKED
CADD FILE NAME
NOTE BOOK
NO.
BY
DATE

EASTBOUND PGL

PROPOSED STRUCTURE
FOR INFORMATION ONLY
SEE BRIDGE PLANS FOR DETAILS

LOW BEAM
ELEV. = 665.25

16.85' CLEAR

PROFILE GRADE
ELEV. = 648.40

EXISTING EB PROFILE GRADE

650.12	650.00	649.87	649.74	649.62	649.50	649.39	649.26	649.14	648.98	648.82	648.69	648.56	648.49	648.41	648.30	648.20	648.07	647.94	647.85	647.76	647.65	647.53	647.40	647.27	647.14	647.01	646.91	646.79	646.65	646.53
146+00	147+00				148+00			149+00			150+00			151+00			152+00			153+00			154+00			155+00			156+00			157+00			158+00			159+00			160+00

PROFILE
STAMPED
PLOTTED
GRADES CHECKED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.
BY
DATE

WESTBOUND PGL

PROPOSED STRUCTURE
FOR INFORMATION ONLY
SEE BRIDGE PLANS FOR DETAILS

LOW BEAM
ELEV. = 665.29

16.84' CLEAR

PROFILE GRADE
ELEV. = 648.45

EXISTING WB PROFILE GRADE

650.14	650.02	649.89	649.75	649.62	649.47	649.33	649.27	649.19	648.98	648.78	648.65	648.53	648.45	648.36	648.24	648.13	648.04	647.95	647.81	647.68	647.59	647.50	647.39	647.28	647.18	647.08	646.96	646.83	646.71
146+00	147+00				148+00			149+00			150+00			151+00			152+00			153+00			154+00			155+00			156+00			157+00			158+00			159+00			160+00

FILE NAME =	USER NAME = mjoost	DESIGNED - MLS	REVISED -
P:\080276\US 51 over I-72\4-CADD\4.2-TR\SHEETS\D774387-sht-plnprf_I-72.dgn		CHECKED - SJK	REVISED -
	PLOT SCALE = 50.0000 ' / in.	DRAWN -	REVISED -
	PLOT DATE = 3/12/2010	CHECKED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE – INTERSTATE 72

SCALE: 1:50 | SHEET NO. 4 OF 4 SHEETS | STA. 145+40 | TO STA. 160+40

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	(58-64HB-1)B-1	MACON	149	20
	US ROUTE 51	CONTRACT NO. 74387		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		