

ILLINOIS DEPARTMENT OF TRANSPORTATION			URBAN	CONSTRUCTION TYPE CODE						
SUMMARY OF QUANTITIES				TOTAL QUANTITIES	ROADWAY 80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 15% STATE 5% CITY		
CODE NO	ITEM	UNIT		I000-2A	I000-2A	I000-2A	Y031-F			
X0326854	PIPE UNDERDRAINS CROSS ROAD	FOOT	208			208				
63800024	GLARE SCREEN BLADES 24"	EACH	794	794						
X0326296	TEMPORARY STORM SEWER 24"	FOOT	288	288						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1726	1671	55					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2943	2698	149	96				
20100500	TREE REMOVAL, ACRES	ACRE	16.5	16.5						
20200100	EARTH EXCAVATION	CU YD	750411	725079	15529	9803				
20800150	TRENCH BACKFILL	CU YD	2864	1600	1096	168				
20900110	POROUS GRANULAR BACKFILL	CU YD	16			16				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	560	560						
25000200	SEEDING, CLASS 2	ACRE	61.25	57.25	2.5	1.5				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5512	5152	225	135				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5512	5152	225	135				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5512	5152	225	135				
25100115	MULCH, METHOD 2	ACRE	32	29	2	1				
25100630	EROSION CONTROL BLANKET	SQ YD	142427	136501	3073	2853				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	12250	11450	500	300				
28000305	TEMPORARY DITCH CHECKS	FOOT	8886	8604	189	93				
28000400	PERIMETER EROSION BARRIER	FOOT	15896	15896						
28000500	INLET AND PIPE PROTECTION	EACH	147	118	23	6				
28100107	STONE RIPRAP, CLASS A4	SQ YD	592	578		14				
28200200	FILTER FABRIC	SQ YD	592	578		14				
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	140076	140076						
30201500	LIME	TON	2550	2550						
30201800	SLAG-MODIFIED PORTLAND CEMENT	TON	149	149						
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	45312	32393	8959	3960				
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	10510	10510						
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	20518	19117	216	1185				
35100100	AGGREGATE BASE COURSE, TYPE A	TON	6413	6354	59					
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	2746	2746						
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	2146	2146						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	203.7	158.6	32.6	12.5				
40600300	AGGREGATE (PRIME COAT)	TON	131	91	29	11				
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2643	11	2238	394				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3						
40600990	TEMPORARY RAMP	SQ YD	36		36					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2963	2963						

PLOT DATE = #DATE#  
FILE NAME = #FILE#  
PLOT SCALE = #SCALE#  
REFERENCE = #REF#

Rev.