

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-16	MADISON	662	8C
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 76311				

ILLINOIS DEPARTMENT OF TRANSPORTATION			URBAN	CONSTRUCTION TYPE CODE						
SUMMARY OF QUANTITIES				TOTAL QUANTITIES	ROADWAY 80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 20% STATE	ROADWAY 80% FEDERAL 15% STATE 5% CITY		
CODE NO	ITEM	UNIT		I000-2A	I000-2A	I000-2A	Y031-F			
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	16	16						
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2461	2461						
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	168	168						
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	18	18						
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	585	420	148	17				
78200300	PRISMATIC CURB REFLECTOR	EACH	17			17				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	81	81						
78200520	BARRIER WALL MARKERS, TYPE B	EACH	31	31						
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1590	405	958	227				
80500100	SERVICE INSTALLATION, TYPE A	EACH	1				1			
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	190				190			
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	680				680			
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	115				115			
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	145				145			
81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	10				10			
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	20				20			
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	25				25			
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	170				170			
81018800	CONDUIT PUSHED, 3 1/2" DIA., GALVANIZED STEEL	FOOT	75				75			
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	8				8			
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	975				975			
81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	10				10			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1			
85706000	INTERSECTION MONITOR UNIT	EACH	1				1			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1745				1745			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	685				685			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4180				4180			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	35				35			

PLOT DATE = #DATE#
PLOT SCALE = #SCALE#
REFERENCE = #REF#

*Specialty Items