

PRECAST FLARED END SECTIONS

STATION	STAGE CONSTRUCTION	12"	15"	18"	21"	24"	30"	36"	24" ERS	36" ERS
		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
<i>US 67</i>										
168+00.00	STAGE 1	1								
169+25.00	STAGE 1	1								
170+54.00	STAGE 1	1								
48+42.00	STAGE 1					2				
SUBTOTALS	STAGE 1	3	0	0	0	2	0	0	0	0
<i>IL III</i>										
1173+20.00	STAGE 1					1				
1173+98.00	STAGE 1	1								
1174+60.00	STAGE 1									2
SUBTOTALS	STAGE 1	1	0	0	0	1	0	0	0	2
<i>FAP 310</i>										
102+00.00	STAGE 1					1				
112+25.00	STAGE 1	1								
113+00.00	STAGE 1					1				
117+50.00	STAGE 1					1				
126+00.00	STAGE 1				1					
127+00.00	STAGE 1					1				
143+00.00	STAGE 1					1				
147+50.00	STAGE 1					1				
163+50.00	STAGE 1					1				
167+50.00	STAGE 1					1				
171+50.00	STAGE 1					1				
175+00.00	STAGE 1					1				
187+00.00	STAGE 1					2				
190+00.00	STAGE 1			2						
190+65.00	STAGE 1						1			
193+00.00	STAGE 1					1				
203+50.00	STAGE 1					1				
219+50.00	STAGE 1					1				
222+50.00	STAGE 1					1				
227+50.00	STAGE 1					1				
<i>Access Rd 1</i>										
42+00.00	STAGE 1			2						
44+50.00	STAGE 1			2						
46+00.00	STAGE 1			2						
51+50.00	STAGE 1			2						
60+25.00	STAGE 1							2		
66+50.00	STAGE 1			1						
73+14.00	STAGE 1			1						
<i>Access Rd 2</i>										
13+30.00	STAGE 1			2						
23+75.00	STAGE 1			2						
40+50.00	STAGE 1			2						
<i>Access Rd 3</i>										
12+00.00	STAGE 1			2						
20+24.00	STAGE 1						1			
21+00.00	STAGE 1								1	
21+62.00	STAGE 1						1			
<i>Ramp A</i>										
04+22.00	STAGE 1					1				
10+15.00	STAGE 1									1
<i>Lagemann Rd</i>										
10+92.00	STAGE 1						2			
19+20.13	STAGE 1					2				
SUBTOTALS	STAGE 1	1	0	20	1	20	5	2	1	1
<i>FAP 310</i>										
226+00.00	STAGE 2					1				
<i>Ramp B</i>										
30+50.00	STAGE 2					1				
SUBTOTALS	STAGE 2	0	0	0	0	2	0	0	0	0
<i>FAP 310</i>										
135+50.00	STAGE 3					1				
177+50.00	STAGE 3					1				
187+00.00	STAGE 3					2				
<i>Beuttel Rd</i>										
09+00.00	STAGE 3									
SUBTOTALS	STAGE 3	0	0	0	0	4	0	0	0	0
TOTALS		5	0	20	1	29	5	2	1	3

FOR INFORMATION ONLY			
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH			
STATION	SQ. FT	DISTANCE	CU YD
<i>US 67 - Stage 1</i>			
167+50.00	0.00		
168+00.00	0.00	50.00	0.00
168+50.00	0.00	50.00	0.20
169+00.00	0.22	50.00	0.82
169+50.00	0.67	50.00	1.45
170+00.00	0.90	50.00	3.19
170+50.00	2.54	50.00	3.63
171+00.00	1.38	50.00	1.97
171+50.00	0.76	50.00	0.70
172+00.00	0.00	100.00	3.06
173+00.00	1.65	50.00	1.93
173+50.00	0.44	50.00	0.40
174+00.00	0.00	50.00	0.00
174+50.00	0.00	50.00	0.00
175+00.00	0.00	50.00	0.00
175+50.00	0.00	50.00	0.00
176+00.00	0.00	50.00	0.00
176+50.00	0.00	50.00	0.00
177+00.00	0.00	10.39	0.00
45+00.00	0.00	50.00	0.00
45+50.00	0.00	50.00	0.00
46+00.00	0.00	50.00	0.00
46+50.00	0.00	50.00	0.00
47+00.00	0.00	50.00	0.00
47+50.00	0.00	50.00	0.00
48+00.00	0.00	50.00	0.00
48+50.00	0.00	50.00	0.04
49+00.00	0.05	100.00	0.08
50+00.00	0.00	50.00	0.00
50+50.00	0.00	50.00	1.98
51+00.00	2.14	50.00	3.61
51+50.00	1.77	50.00	3.88
52+00.00	2.43	50.00	4.79
52+50.00	2.75	50.00	5.25
53+00.00	2.92	50.00	6.59
53+50.00	4.20	50.00	8.46
54+00.00	4.94	50.00	9.84
54+50.00	5.70	50.00	11.69
55+00.00	6.93	50.00	12.92
55+50.00	7.03	50.00	12.83
56+00.00	6.84		
Total			99.3

FOR INFORMATION ONLY			
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH			
STATION	SQ. FT	DISTANCE	CU YD
<i>IL III - Stage 1</i>			
1172+56.10	0.00	43.90	0.00
1173+00.00	0.00	50.00	0.00
1173+50.00	0.00	50.00	0.00
1174+00.00	0.00	50.00	1.31
1174+50.00	1.41	50.00	3.98
1175+00.00	2.89	50.00	5.52
1175+50.00	3.08	50.00	4.37
1176+00.00	1.65	50.00	2.96
1176+50.00	1.56	50.00	5.09
1177+00.00	3.95	50.00	6.61
1177+50.00	3.20	50.00	6.74
1178+00.00	4.09	50.00	6.90
1178+50.00	3.37	50.00	6.12
1179+00.00	3.24	40.00	5.53
1179+40.00	4.23		
Total			55.1
<i>FOR INFORMATION ONLY</i>			
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH			
STATION	SQ. FT	DISTANCE	CU YD
<i>IL III - Stage 2</i>			
1172+56.10	0.00	43.90	0.00
1173+00.00	0.00	50.00	0.00
1173+50.00	0.00	50.00	0.00
1174+00.00	0.00	50.00	2.84
1174+50.00	3.07	50.00	6.96
1175+00.00	4.45	50.00	8.53
1175+50.00	4.77	50.00	7.54
1176+00.00	3.38	50.00	4.62
1176+50.00	1.61	50.00	4.74
1177+00.00	3.51	50.00	7.17
1177+50.00	4.24	50.00	8.51
1178+00.00	4.96	50.00	10.19
1178+50.00	6.06	50.00	11.34
1179+00.00	6.20	40.00	8.95
1179+40.00	5.89		
Total			81.4

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH			
<i>US 67 (Godfrey Road)</i>		CADD (sq ft)	SO YD
169+00.00	to 171+75.00	3144.39	349.4
172+25.00	to 173+75.00	2767.48	307.5
50+75.00	to 56+34.00	12550.74	1394.5
		SubTotal	2052
<i>Business US 67 (IL III)</i>			
1174+25.00	to 1179+40.00	11683	1298.1
		SubTotal	1299
		Total	3351

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULES OF QUANTITIES

SCALE: NO SCALE  
DATE: 09-04-09

DRAWN BY: C.J.C.  
CHECKED BY: J.J.C.