

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 031-0041(P) 401-2BR X071-2A	SN 031-0040(P) 1-2BR X071-2A	SN 031-0039(P) 1BR X071-2A
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	165	165		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	235	235		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	410	106	140	164
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
50105220	PIPE CULVERT REMOVAL	FOOT	66	66		
50200100	STRUCTURE EXCAVATION	CU YD	681	219	226	236
50300100	FLOOR DRAINS	EACH	8		8	
50300225	CONCRETE STRUCTURES	CU YD	179.4	56.2	61.5	61.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	602.7	204.8	189	208.9
50300260	BRIDGE DECK GROOVING	SQ YD	1244	422	386	436
50300280	CONCRETE ENCASEMENT	CU YD	13.2	6.6	6.6	
50300300	PROTECTIVE COAT	SQ YD	1594	552	488	554
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	0.46	0.2	0.34
50500505	STUD SHEAR CONNECTORS	EACH	2916	846	972	1098
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	158740	53620	50690	54430
50800515	BAR SPLICERS	EACH	1071	56	486	529
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	693			693
51201800	FURNISHING STEEL PILES HP14X73	FOOT	1520	580	940	
51202305	DRIVING PILES	FOOT	2213	580	940	693
51203200	TEST PILE METAL SHELLS	EACH	1			1
51203800	TEST PILE STEEL HP14X73	EACH	4	2	2	
51205200	TEMPORARY SHEET PILING	SQ FT	3377		1217	2160
51500100	NAME PLATES	EACH	3	1	1	1
52100520	ANCHOR BOLTS, 1"	EACH	72	24	24	24
54213453	END SECTIONS 18"	EACH	4	2	2	
54213471	END SECTIONS 36"	EACH	2	2		
5421A036	PIPE CULVERTS, CLASS A, TYPE 1 36" (TEMPORARY)	FOOT	160	160		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	119	43	76	
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	57	57		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	218	63	76	79