

RESURFACING SCHEDULE											
LOCATION			BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE	HOT-MIX ASPHALT BINDER COURSE	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	HOT-MIX ASPHALT SHOULDERS		TEMPORARY RAMP
									LT	RT	
STATION	TO	STATION	TON	TON	TON	TON	SQ YD	SQ YD	TON		SQ YD
234+37.5	TO	235+00	0.1	0.2	12.8	0.0	42.3		1.6	15.6	
235+00	TO	235+50	0.1	0.2	10.3	0.0	33.8		5.8	12.4	
235+50	TO	236+00	0.1	0.2	27.0	19.6	33.8		11.2	12.4	
236+00	TO	236+29	0.1	0.1	6.0	28.2	19.6		7.8	7.2	
236+29	TO	236+35					4.1	24			25
236+35	TO	236+83.5					32.8				
237+16.5	TO	23+65					32.8				
237+65	TO	237+71					4.1	24			25
237+71	TO	238+00	0.1	0.1	6.0	26.9	19.6		14.4	7.2	
238+00	TO	238+50	0.1	0.2	10.3	17.3	33.8		18.1	12.5	
238+50	TO	239+00	0.1	0.2	22.7	0.0	33.8		7.6	12.5	
239+00	TO	239+50	0.1	0.2	10.3	0.0	33.8		2.1	12.5	
239+50	TO	239+62.5	0.1	0.1	2.6	0.0	8.5		0	3.1	
TOTAL =			0.9	1.5	108	92	333	48	164		50

STAGING SCHEDULE						
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	TEMPORARY RUMBLE STRIP	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED)
	FOOT	FOOT	EACH	EACH	EACH	EACH
STAGE I	425		2			
STAGE II		312.5		2		
STAGE I & II					6	1
TOTAL =	425	312.5	2	2	6	1

GUARDRAIL SCHEDULE							
LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
NB ELDRED-HILLVIEW RD				3	2	2	
SB ELDRED-HILLVIEW RD				3	2	2	
NW QUADRANT	87.5	1	1				1
NE QUADRANT		1	1				1
SW QUADRANT		1	1				1
SE QUADRANT	87.5	1	1				1
TOTAL =	175	4	4	6	4	4	4

FILE NAME =	USER NAME = tharpr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SN 031-0010(E) 0039(P), SECTION 1BR			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pw_work\p\dot\tharpr1\dms52692\0876	10-sht-schedule.dgn	DRAWN -	REVISED -					739	1BR, 1-2BR, 401-2BR	GREENE	150	112
	PLOT SCALE = 50.000' / IN.	CHECKED -	REVISED -		SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.			CONTRACT NO. 76410				
	PLOT DATE = 3/25/2010	DATE -	REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT					