

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM #4

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	3.00	444.76	444.76
⊙ Brg. S. Abut.	236+66.25	3.00	444.77	444.77
A	236+76.25	3.00	444.79	444.84
B	236+86.25	3.00	444.80	444.90
C	236+96.25	3.00	444.81	444.93
D	237+06.25	3.00	444.82	444.93
E	237+16.25	3.00	444.81	444.89
F	237+26.25	3.00	444.80	444.84
⊙ Brg. N. Abut.	237+33.75	3.00	444.78	444.78
Bk. N. Abut.	237+35.00	3.00	444.78	444.78

BEAM #5

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	9.00	444.67	444.67
⊙ Brg. S. Abut.	236+66.25	9.00	444.67	444.67
A	236+76.25	9.00	444.70	444.75
B	236+86.25	9.00	444.71	444.80
C	236+96.25	9.00	444.72	444.83
D	237+06.25	9.00	444.72	444.83
E	237+16.25	9.00	444.72	444.80
F	237+26.25	9.00	444.70	444.74
⊙ Brg. N. Abut.	237+33.75	9.00	444.69	444.69
Bk. N. Abut.	237+35.00	9.00	444.69	444.69

BEAM #6

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	15.00	444.56	444.56
⊙ Brg. S. Abut.	236+66.25	15.00	444.56	444.56
A	236+76.25	15.00	444.59	444.64
B	236+86.25	15.00	444.60	444.69
C	236+96.25	15.00	444.61	444.72
D	237+06.25	15.00	444.61	444.72
E	237+16.25	15.00	444.61	444.69
F	237+26.25	15.00	444.59	444.63
⊙ Brg. N. Abut.	237+33.75	15.00	444.58	444.58
Bk. N. Abut.	237+35.00	15.00	444.58	444.58

Notes:
1. Elevations are at Top of Concrete.
2. See Sheet 5 of 23 for elevation locations.

DESIGNED	B.G.H.
CHECKED	L.D.G.
DRAWN	K.H.L.
CHECKED	B.G.H.

TOP OF SLAB ELEVATIONS

SHEET NO. 7	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	739	1BR	GREENE	150	128
23 SHEETS	S.N. 031-0039		CONTRACT NO. 76410		
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					