

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE										BOX CULVERT X028-2A 80% FED 20% STATE	RETAINING WALLS Y007 80% FED 20% STATE	
				ROADWAY I000-2A				TRAFFIC SIGNALS Y031-1F			UTILITIES Y060					
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY E. CHURCH ST. 80% FED 10% STATE 10% CITY	MADISON COUNTY MID BLOCK CROSSING 80% FED 20% CITY	ST. CLAIR COUNTY MORRISON AVE. 80% FED 20% STATE	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY			MADISON COUNTY
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE			80% FED 20% STATE
CODE NO	ITEM	UNIT														
X0326820	INLETS, SPECIAL, TYPE E, 4' X 4'	EACH	13	1		12										
X0326821	INLETS, SPECIAL, TYPE E, 4' X 5'	EACH	8			8										
X0326822	INLETS, SPECIAL, TYPE E, 4' X 6'	EACH	4	3		1										
X0326823	INLETS, SPECIAL, TYPE E, DOUBLE 4' X 4'	EACH	1			1										
D2012204	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 3" CALIPER, BALLED AND BURLAPPED	EACH	4	4												
XX004018	REMOVE AND RELAY BRICK SIDEWALK	SQ FT	35			35										
XZ137300	TEMPORARY SHORING	L SUM	1			1										
X0326826	WATER MAIN TO BE ABANDONED, 8"	FOOT	2095								470	1625				
X0326825	WATER MAIN TO BE ABANDONED, 6"	FOOT	2803								88	2715				
X0326824	WATER MAIN TO BE ABANDONED, 4"	FOOT	2936								40	2896				
X0326827	WATER METER ASSEMBLY, 1"	EACH	80									80				
X0326828	WATER METER ASSEMBLY, 2"	EACH	1									1				
X6065701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	25			25										
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2074			2074										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2048			2048										
20200100	EARTH EXCAVATION	CU YD	37949	2107		35842										
20800150	TRENCH BACKFILL	CU YD	12402	1669		4669					394	5670				
*25000115	SEEDING, CLASS 1B	ACRE	6	1		5										
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	567	83		484										
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	567	83		484										
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	567	83		484										
*25100105	MULCH, METHOD 1	ACRE	6	1		5										
*25100630	EROSION CONTROL BLANKET	SQ YD	7183	759		6424										
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	950	139		811										
28000315	AGGREGATE DITCH CHECKS	TON	192	42		150										
28000400	PERIMETER EROSION BARRIER	FOOT	2191	313		1878										
28000500	INLET AND PIPE PROTECTION	EACH	130	18		112										
28100105	STONE RIPRAP, CLASS A3	SQ YD	81	50		31										
28100107	STONE RIPRAP, CLASS A4	SQ YD	778	327		338										
28100109	STONE RIPRAP, CLASS A5	SQ YD	143	143									113			
28200200	FILTER FABRIC	SQ YD	1065	527		369										
X0326855	WATER METER TO BE REMOVED	EACH	5													
X0539700	TREE FRAME AND GRATE	EACH	2			2						5				

\* Specialty Items Rev.

Rev. 2-18-10

FILE NAME =	USER NAME = keplercl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pw\work\PIWIDOT\KEPLARCL\dms79887\08	6838-shr-plan.dgn	DRAWN -	REVISED -			600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	4	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 76830					
	PLOT DATE = 11/19/2009	DATE -	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					