



- NOTES:
1. TYPICAL TREE SPACING IS 20' X 20'.
  2. TREES SHALL NOT BE LOCATED WITHIN 10' OF ANY UNDERGROUND UTILITY.
  3. TREES SHALL NOT BE PLACED ON SLOPES STEEPER THAN 3:1.



**KEY**

- ✕ TREES TO BE REMOVED
- AS 2-1/2" TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED
- OP 2-1/2" TREE, QUERCUS PALUSTRIS (PIN OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED
- OR 2-1/2" TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED
- CC 2" TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED
- MS 2" TREE, MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED
- PS 3" EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 3" CALIPER, BALLED AND BURLAPPED

**LANDSCAPE SCHEDULE**

STATION	STATION	T-ACER SACR 2-1/2 (UNIT)	T-QUERCUS PALUS 2-1/2 (UNIT)	T-QUERCUS RUBRA 2-1/2 (UNIT)	T-CERCIS CAN TF 2 (UNIT)	T-MALUS SND TF 2 (UNIT)	E-PINUS STROBUS 3 (UNIT)	TREE REMOV 6-15 (UNIT)	TREE REMOV OVER 15 (UNIT)
102+00	109+75				9		4		
109+75	112+00							8	
112+00	122+00							454	48
122+00	132+00	4	6	3	11	11		1270	704
132+00	142+00					10		342	1074
142+00	152+00	9			11				
152+00	157+00				2				132
<b>TOTAL</b>		<b>13</b>	<b>6</b>	<b>3</b>	<b>33</b>	<b>21</b>	<b>4</b>	<b>2074</b>	<b>1958</b>

FILE NAME = 0878830-sh1-1ndsep.dgn	USER NAME = lde	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1:20	CHECKED -	REVISED -
	PLOT DATE = 12/17/2009	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**LANDSCAPE PLAN**

SCALE: 1:20 SHEET NO. OF SHEETS STA. 100+00.00 TO STA. 104+00.00

F.A.P. RTE. 600	SECTION 60-(30.31.128)-1	COUNTY	TOTAL SHEETS 399	SHEET NO. 229
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 76830				