

SUMMARY OF QUANTITIES

					URBAN 100% STATE		
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	15TH STREET BRIDGE STR NO
					J000-2A	Y031-1F	082-0377 X271-2A
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	910	910		
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	299	299		
	42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	6,451	6,451		
	42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10½" (JOINTED)	SQ YD	4,592	4,592		
	42001300	PROTECTIVE COAT	SQ YD	21,605	21,605		
	42100340	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	1,516	1,516		
	42100940	PAVEMENT REINFORCEMENT 12"	SQ YD	1,516	1,516		
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	66	66		
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	208	208		
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	10,441	10,441		
	42400800	DETECTABLE WARNINGS	SQ FT	138	138		
	44000100	PAVEMENT REMOVAL	SQ YD	14,562	14,562		
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 ¼"	SQ YD	1,191	1,191		
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	153	153		
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	388	388		
	44000300	CURB REMOVAL	FOOT	881	881		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5,779	5,779		
	44000600	SIDEWALK REMOVAL	SQ FT	14,338	14,338		
	44001980	CONCRETE BARRIER REMOVAL	FOOT	59	59		
	44003100	MEDIAN REMOVAL	SQ FT	4,156	4,156		
	44004250	PAVED SHOULDER REMOVAL	SQ YD	5,783	5,783		
	44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	100	100		
	44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	100	100		
	44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	100	100		
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	164	164		
	48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	56	56		
	48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10½"	SQ YD	2,698	2,698		
	48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	1,863	1,863		
	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1

• DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = jmsarno	DESIGNED OP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN OP	REVISED -		64	82-1-2HB	ST. CLAIR	345	6			
	PLOT SCALE = 1,0000' / IN.	CHECKED DBM	REVISED -		SCALE: NONE SHEET NO. 2 OF 11 SHEETS STA. TO STA.			CONTRACT NO. 76C49				
	PLOT DATE = 3/19/2010	DATE 03/19/10	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							