

SUMMARY OF QUANTITIES

					URBAN 100% STATE		
					ROADWAY	TRAFFIC SIGNALS	15TH STREET BRIDGE STR NO 082-0377
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	J000-2A	Y031-1F	X271-2A
	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1
	50157300	PROTECTIVE SHIELD	SQ YD	1,402			1,402
	50200100	STRUCTURE EXCAVATION	CU YD	4,379			4,379
	50300225	CONCRETE STRUCTURES	CU YD	1,254.6			1,254.6
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	825.8			825.8
	50300260	BRIDGE DECK GROOVING	SQ YD	1,521			1,521
	50300285	FORM LINER TEXTURED SURFACE	SQ FT	4,600			4,600
	50300300	PROTECTIVE COAT	SQ YD	1,998			1,998
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
	50500505	STUD SHEAR CONNECTORS	EACH	3,771			3,771
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	350,190			350,190
	50800515	BAR SPLICERS	EACH	119			119
	50901730	BRIDGE FENCE RAILING	FOOT	286			286
	50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	287			287
	51200959	FURNISHING METAL SHELL PILES 14" x 0.312"	FOOT	9,225			9,225
	51201900	FURNISHING STEEL PILES HP 14X89	FOOT	3,744			3,744
	51202305	DRIVING PILES	FOOT	12,969			12,969
	51204650	PILE SHOES	EACH	39			39
	51203900	TEST PILE STEEL HP 14X89	EACH	39			39
	51500100	NAME PLATES	EACH	1			1
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	122			122
	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	15			15
	52100530	ANCHOR BOLTS, 1/4"	EACH	16			16
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2		
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION 15"	EACH	2	2		
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	2	2		
	54248510	CONCRETE COLLAR	CU YD	10	10		
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	178	178		
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	129	129		
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	74	74		

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = pmsorno	DESIGNED OP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
%FILE#	PLOT SCALE = 1.0000" / 1" IN.	DRAWN OP	REVISED -			64	82-1-2HB	ST. CLAIR	345	7
	PLOT DATE = 3/19/2010	CHECKED DBM	REVISED -			SCALE: NONE SHEET NO. 3 OF 11 SHEETS STA. TO STA.		CONTRACT NO. 76C49		
				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						

Rev.