

SUMMARY OF QUANTITIES

					URBAN 100% STATE		
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	15TH STREET BRIDGE STR NO 082-0377
					J000-2A	Y031-1F	X271-2A
	60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4		
	60221100	MANHOLES, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9		
	60223800	MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
	60224446	MANHOLES, TYPE A, 7' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2		
	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2		
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	5	5		
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	8	8		
	60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1		
	60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	1	1		
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	15	15		
	60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4		
	60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	6	6		
	60500040	REMOVING MANHOLES	EACH	3	3		
	60500060	REMOVING INLETS	EACH	25	25		
	60602500	CONCRETE GUTTER, TYPE A	FOOT	387	387		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,271	5,271		
	60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	29	29		
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	639	639		
	60622800	CONCRETE MEDIAN, TYPE SM-6.12	SQ FT	446	446		
*	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	775.0	775.0		
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
*	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1		
*	63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	FOOT	4	4		
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
	63200310	GUARDRAIL REMOVAL	FOOT	1,419	1,419		
	63302400	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1		
	63500105	DELINEATORS	EACH	27	27		
	63500120	DELINEATOR REMOVAL	EACH	11	11		
	63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	153	153		

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = pmsarrio	DESIGNED OP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\$FILEAS		DRAWN OP	REVISED -		SCALE: NONE	SHEET NO. 5 OF 11 SHEETS	STA.	TO STA.	64	82-1-2HB	ST. CLAIR	345	9
	PLOT SCALE = 1,0000' / IN.	CHECKED DBM	REVISED -								CONTRACT NO. 76C49		
	PLOT DATE = 3/19/2010	DATE 03/19/10	REVISED -								ILLINOIS FED. AID PROJECT		