

## SUMMARY OF QUANTITIES

					URBAN 100% STATE		
					ROADWAY	TRAFFIC SIGNALS	15TH STREET BRIDGE STR NO 082-0377
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	J000-2A	Y031-1F	X271-2A
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	17	17		
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		2	
*	87100160	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	FOOT	719		719	
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,246		1,246	
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,254		1,254	
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,064		7,064	
*	87301405	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 16 1 PAIR	FOOT	2,584		2,584	
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	280		280	
*	87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	1		1	
*	87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1		1	
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1	
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1	
*	87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1	
*	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1	
*	87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		1	
*	87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1		1	
*	87702730	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 50 FT.	EACH	1		1	
*	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7		7	
*	87800300	CONCRETE FOUNDATION, TYPE E 24-INCH DIAMETER	FOOT	3		3	
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10		10	
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	85		85	
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	18		18	
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	11		11	
*	88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	4		4	
*	88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4		4	
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8	
*	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	37		37	
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8	
*	88600100	DETECTOR LOOP, TYPE I	FOOT	2,809		2,809	
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8	

\* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = pmsarno	DESIGNED OP	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8FILEA8	PLOT SCALE = 1:8000 1/4 IN.	DRAWN OP	REVISED -			64	82-1-2HB	ST. CLAIR	345	13
	PLOT DATE = 3/19/2010	CHECKED DBM	REVISED -			SCALE: NONE SHEET NO. 9 OF 11 SHEETS STA. TO STA.		CONTRACT NO. 76C49		
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

*Rev.*