

FENCE ITEM SCHEDULE

SHEET	STATION	TO	STATION	CHAIN LINK FENCE, 6'	CHAIN LINK GATES, 6' X
				FOOT	12' DOUBLE
15TH STREET					
PLAN-1	3+00.00	TO	8+50.00	436	-
PLAN-2	8+50.00	TO	13+92.79	313	-
RAMP E					
PLAN-3	10+91.65	TO	111+30.00	624	1
PLAN-4	7+50.00	TO	508+60.00	2	-
PLAN-5	508+60.00	TO	105+15.26	-	-
ST. CLAIR AVE AND RAMP A & RAMP B					
PLAN-6	28+61.00	TO	35+50.00	582	1
PLAN-7	38+00.00	TO	43+50.00	202	-
PLAN-8	43+50.00	TO	49+00.00	-	-
RAMP B					
PLAN-9	11+00.00	TO	15+41.39	39	-

TOTALS	2,198	2
---------------	--------------	----------

CONCRETE CURB AND GUTTER AND MEDIAN SCHEDULE

SHEET	STATION	TO	STATION	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SM-6.12
				FOOT	FOOT	FOOT	SQ FT	SQ FT
15TH STREET								
PLAN-1	3+00.00	TO	8+50.00	43	1,308	-	250	446
PLAN-2	8+50.00	TO	13+92.79	206	1,130	-	-	-
RAMP E								
PLAN-3	10+91.65	TO	111+30.00	-	1,655	-	59	-
PLAN-4	7+50.00	TO	508+60.00	138	1	-	-	-
PLAN-5	508+60.00	TO	105+15.26	-	-	-	-	-
ST. CLAIR AVE AND RAMP A & RAMP B								
PLAN-6	28+61.00	TO	35+50.00	-	959	29	330	-
PLAN-7	38+00.00	TO	43+50.00	-	199	-	-	-
PLAN-8	43+50.00	TO	49+00.00	-	-	-	-	-
RAMP B								
PLAN-9	11+00.00	TO	15+41.39	-	19	-	-	-

TOTALS	387	5,271	29	639	446
---------------	------------	--------------	-----------	------------	------------

NOTE :
1. DEPRESSED CURB AND GUTTER THROUGH ENTRANCES SHALL BE MEASURED FOR PAYMENT AS COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

SIDEWALK SCHEDULE

SHEET	STATION	TO	STATION	PORTLAND CEMENT CONCRETE SIDEWALK - 4"	DETECTABLE WARNINGS
				SQ FT	SQ FT
15TH STREET					
PLAN-1	3+00.00	TO	8+50.00	4,142	68
PLAN-2	8+50.00	TO	13+92.79	4,202	70
RAMP E					
PLAN-3	10+91.65	TO	111+30.00	483	-
PLAN-4	7+50.00	TO	508+60.00	-	-
PLAN-5	508+60.00	TO	105+15.26	-	-
ST. CLAIR AVE AND RAMP A & RAMP B					
PLAN-6	28+61.00	TO	35+50.00	1,614	-
PLAN-7	38+00.00	TO	43+50.00	-	-
PLAN-8	43+50.00	TO	49+00.00	-	-
RAMP B					
PLAN-9	11+00.00	TO	15+41.39	-	-

TOTALS	10,441	138
---------------	---------------	------------

PERMANENT SEEDING ITEM (SEEDING AND MULCHING) SCHEDULE

SHEET	STATION	TO	STATION	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2
				ACRE	POUND	POUND	POUND	ACRE
15TH STREET								
PLAN-1	3+00.00	TO	8+50.00	1.25	113	113	113	1.25
PLAN-2	8+50.00	TO	13+93.34	0.75	68	68	68	0.75
RAMP E								
PLAN-3	10+91.65	TO	111+30.00	0.75	68	68	68	0.75
PLAN-4	7+50.00	TO	508+60.00	0.75	68	68	68	0.75
PLAN-5	508+60.00	TO	106+72.50	0.25	23	23	23	0.25
ST. CLAIR AVE AND RAMP A & RAMP B								
PLAN-6	28+61.00	TO	35+50.00	1.25	113	113	113	1.25
PLAN-7	38+00.00	TO	43+50.00	2.00	180	180	180	2.00
PLAN-8	43+50.00	TO	40+04.59	0.25	23	23	23	0.25
RAMP B								
PLAN-9	11+00.00	TO	18+33.27	2.00	180	180	180	2.00

TOTALS	9.25	836	836	836	9.25
---------------	-------------	------------	------------	------------	-------------

NOTE :
1. ALSO SEE LANDSCAPING PLANS FOR ADDITIONAL SEEDING QUANTITIES.