

PAVEMENT MARKING SCHEDULE (SAFETY AREA 1)

LOCATION		THERMO PAVEMENT MARKING - 4"				THERMO PAVEMENT MARKING - 12"		THERMO. P.M. - LETTERS AND SYMBOLS (SQ FT)
		WHITE EDGE LINE (FOOT)	WHITE SKIP-DASH (FOOT)	DOUBLE YELLOW LINE (FOOT)	WHITE LANE LINE (FOOT)	YELLOW DIAGONALS (FOOT)	WHITE STOP BAR (FOOT)	
STA	STA							
153+00	157+00	800.0	8.0	1,366.0	0.0	77.0	0.0	0.0
157+00	163+00	1,003.0	76.0	1,652.0	230.0	77.0	0.0	62.4
163+00	166+23.05	647.0	0.0	1,142.0	0.0	65.0	0.0	0.0
HOOTS CHAPEL ROAD N & S		0.0	0.0	0.0	0.0	0.0	35.0	0.0
SUBTOTAL		2,450.0	84.0	4,160.0	230.0	219.0	35.0	0.0
GRAND TOTAL		6,924.0				254.0		62.4

RAISED REFLECTIVE PAVEMENT MARKERS AND REMOVAL (SAFETY AREA 1)

LOCATION		WHITE CRYSTAL (EACH)	DOUBLE AMBER (EACH)	RRPM REMOVAL (EACH)
STA.	STA.			
153+00	157+00	16	3	6
157+00	163+00	25	6	9
163+00	166+23.05	14	3	5
SUBTOTAL		55	12	20
TOTAL		67		20

SHORT-TERM PAVEMENT MARKING AND WORK ZONE PM REMOVAL (SAFETY AREA 1)

LOCATION		SHORT-TERM PM (FOOT)	WORK ZONE PM REMOVAL (SQ FT)
STA.	STA.		
153+00	157+00	448	37.3
157+00	163+00	672	56.0
163+00	166+23.05	384	32.0
TOTAL		1504	125.3

SIGN SCHEDULE (SAFETY AREA 1)

LOCATION	OFFSET	SIGN	SIZE	POST	DESCRIPTION	SIGN PANEL		POST LENGTH
						TYPE 1	TYPE 2	
STATION						SQ FT	SQ FT	FT
153+00.00	20(LT)	W14-3	48" X 36"	WOOD	NO PASSING ZONE		12.00	16
159+79.27		R1-I	30" X 30"	WOOD	STOP	6.25		14
159+85.12		R1-I	30" X 30"	WOOD	STOP	6.25		14
165+48.00	20(RT)	W14-3	48" X 36"	WOOD	NO PASSING ZONE		12.00	16.5
TOTALS						13	24	61