

80% FED.
20% STATE

SUMMARY OF QUANTITIES

80% FED.
20% STATE

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27.9	27.9		
40600300	AGGREGATE (PRIME COAT)	TON	134	134		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1716.6	1716.6		
40600990	TEMPORARY RAMP	SO YD	1275	1275		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3743	3743		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.05	0.05		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14.2	14.2		
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	40877	40877		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	112.9	112.9		
44000400	GUTTER REMOVAL	FOOT	1100	1100		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	156.5	156.5		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	128.8	128.8		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	1143.2	1143.2		
60602500	CONCRETE GUTTER, TYPE A	FOOT	1100	1100		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	418.75	418.75		
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	98.75	98.75		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
63200310	GUARDRAIL REMOVAL	FOOT	378	378		
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	37.5	37.5		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11280	11280		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1486	1486		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	54183	54183		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	632	632		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1182	1182		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48	48		

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	-----	-----
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1240.8	1240.8		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1486	1486		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	54183	54183		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	632	632		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	410	410		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1182	1182		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48	48		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	170	170		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	443	443		
* 78200300	PRISMATIC CURB REFLECTOR	EACH	60	60		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	21	21		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	443	443		
80300100	LOCATING UNDERGROUND CABLE	FOOT	633	633		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2943	2943		
20048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
	* Specialty Items					

FILE NAME =	USER NAME = kerlesal	DESIGNED -	REVISED -
c:\pwwork\VPWIDOT\KARLASAL\d0155566\d0155566.dgn	6d44-shr-plen.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8" = 107.3171' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/2/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9251	26-IRS-3	ST. CLAIR	37	4
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 76D44	

Re