GUARDRAIL

LOCATION NUMBER	LOCAITION DESCRIPTION	SPBGR, TYPE A 6 FT POSTS (FOOT)	SPBGR, ATTACHED TO STRUCTURE (FT)	TBT, TYPE 1 (SPEC) TANGENT (EACH)	SPBGR (SHORT RADIUS) (FT)
1	APPROXMATELY 250' EAST OF CENTREVILLE AVE.	375.00		2	
2	BOX CULVERT AT IL 13/IL 158 AND IL 159	12.50	67.5	2	37.5
3	BOX CULVERT EAST OF HEARTHSIDE	31.25	31.25	2	
	TOTAL	418.75	98.75	6	37.5

REFLECTOR AND TERMINAL MARKERS

LOCATION NUMBER	LOCAITION DESCRIPTION	REFLECTOR MARKERS, TYPE A (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)
1	APPROXMATELY 250' EAST OF CENTREVILLE AVE.	6	2
2	BOX CULVERT AT IL 13/IL 158 AND IL 159	10	2
3	BOX CULVERT EAST OF HEARTHSIDE	5	2
	TOTAL	21	6

PARTIAL DEPTH PATCHING

LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	HMA SURFACE REMOVAL 2 1/4" (SQ YD)	HMA INCIDENTAL (TONS)	408 BIT. MATERIALS (PRIME COAT) (TONS)
STA. 111+75 (EB)	4	20	8.9	8.9	1.1	0.01
STA. 125+45 (LTL)	12	30	40.0	40.0	5.0	0.01
STA. 140+79 (LT TURN LANE)	4	24	10.7	10.7	1.3	0.01
143+96 (WB)	6	50	33.3	33.3	4.2	0.01
STA. 147+13 (WB)	6	30	20.0	20.0	2.5	0.01
				112.9	14.2	0.05

FILE NAME = c:\pw_work\PWIDOT\KARLASAL\d0155566\d876d44-sht-plan.dgn	USER NAME = karlasal	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 187.3171 ' / IN.	DRAWN -	REVISED -			9251	26-1BS-3	ST. CLAIR	37	15
	PLOT DATE = 3/3/2010	CHECKED -	REVISED -					CONTRACT NO. 76D44		
		DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		