

SUMMARY OF QUANTITIES

100% STATE

100% STATE

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|--------|------------------------|-------|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 1000 | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 16 | 16 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 77 | 77 | |
| 40600635 | LEVELING BINDER (MACHINE METHOD), N70 | TON | 1474 | 1474 | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 391 | 391 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 325 | 325 | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 2564 | 2564 | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 485 | 485 | |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | SQ YD | 29465 | 29465 | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 34 | 34 | |
| 44200120 | PAVEMENT PATCHING, TYPE II, 10 INCH | SQ YD | 610 | 610 | |
| 44200126 | PAVEMENT PATCHING, TYPE IV, 10 INCH | SQ YD | 447 | 447 | |
| 44200202 | PAVEMENT PATCHING, TYPE II, 17 INCH | SQ YD | 35 | 35 | |
| 44200206 | PAVEMENT PATCHING, TYPE IV, 17 INCH | SQ YD | 158 | 158 | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 407 | 407 | |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 2237 | 2237 | |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 4 | 4 | |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 34 | 34 | |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 1 | 1 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 50 | 50 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100310 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701421 | L SUM | 1 | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 4807 | 4807 | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 156 | 156 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 23807 | 23807 | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 66 | 66 | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 214 | 214 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 411 | 411 | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 156 | 156 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 23807 | 23807 | |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 66 | 66 | |

| SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|------|------------------------|------|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 1000 | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 214 | 214 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 239 | 239 | |
| * 78200300 | PRISMATIC CURB REFLECTOR | EACH | 46 | 46 | |
| * 78200530 | BARRIER WALL MARKERS, TYPE C | EACH | 29 | 29 | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 1 | 1 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 143 | 143 | |
| * 7800200 | PAINT PAVEMENT MARKING CURB | FOOT | 661 | 661 | |

**Specialty Items*

| | | | | | | | | | | | |
|-------------|----------------------|----------------|---------------|---|------------------------------|---|--------------------|----------------------------|--------------------|--------------------------|--|
| FILE NAME = | USER NAME = #USER# | DESIGNED - --- | REVISED - --- | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P. RTE. 805 | SECTION 146RS-3 | COUNTY ST. CLAIR | TOTAL SHEETS 21 | SHEET NO. 3 | |
| #FILE# | | DRAWN - --- | REVISED - --- | | | | | | | | |
| | PLOT SCALE = #SCALE# | CHECKED - --- | REVISED - --- | | | | | | | | |
| | PLOT DATE = #DATE# | DATE - --- | REVISED - --- | | | | | | | | |
| | | | | | | SCALE: ----- | | SHEET NO. -- OF --- SHEETS | | STA. ----- TO STA. ----- | |
| | | | | | | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | | |
| | | | | | | CONTRACT NO. 76D57 | | | | | |