

PAVING SCHEDULE

STATIONING			BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	LEVELING BINDER MACHINE METHOD N70 (TON)	HMA SURFACE COURSE MIX "D", N70 (TON)	INCIDENTAL HMA SURFACING (TON)	HMA SURFACE REMOVAL - 2" (SQ YD)	AGGREGATE WEDGE SHLDRS., TYPE B (TON)	HMA SHOULDERS (TON)
73+90.36	TO	88+00.00	3.6	17.3	459.9	690.0	65.0	0.0	92.4	404.5
88+00.00	TO	96+84.80	3.2	15.4	307.5	461.0	379.1	0.0	58.4	284.5
96+84.80	TO	112+49.21	RESURFACING OMISSION							
112+49.21	TO	118+00.00	1.7	8.0	123.5	246.8	0.0	5355.0	66.9	304.5
118+00.00	TO	133+00.00	4.6	21.9	336.0	672.0	0.0	14583.5	91.0	829.5
133+00.00	TO	139+23.73	2.0	9.8	158.9	318.0	40.8	6538.5	74.3	301.5
139+23.73	TO	144+84.05	RESURFACING OMISSION							
144+84.05	TO	146+68.52	0.9	4.5	88.1	176.3	0.0	2988.0	24.0	112.5
			16.0	77.0	1474.0	2564.0	485.0	29465.0	407.0	2237.0

PAVEMENT MARKING SCHEDULE

STATION			THERMOPLASTIC PAVEMENT MARKING LINE-4" (FOOT)			THERMOPLASTIC PAVEMENT MRKNG LETTERS AND SYMBOLS (SQ FT)	THERMOPLASTIC PAVEMENT MARKING LINE-12" (FOOT)	THERMOPLASTIC PAVEMENT MARKING LINE-24" (FOOT)	PAINT PAVEMENT MARKING CURB (FOOT)	TEMPORARY PAVEMENT MARKING LINE-4" (FOOT)			TEMPORARY PAVT. MRKNG LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING LINE-12" (FOOT)	TEMPORARY PAVEMENT MARKING LINE-24" (FOOT)	SHORT TERM PAVEMENT MARKING (FOOT)	RAISED RELECTIVE PAVEMENT MARKERS (EACH)	RAISED RELECTIVE PAVT. MRK. REMOVAL (EACH)	WORK ZONE PAVEMENT MRK. REM. (SQ FT)
			SOLID WHITE	SKIP-DASH WHITE	SOLID YELLOW					SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW							
73+90.15	TO	80+40.01	1450	325	1450	31.2			167	1450	325	1450	31.2			597.9	48	20	49.8
80+40.01	TO	88+00.00	1520	380	1520				72	1520	380	1520				699.2	19	19	58.3
88+00.00	TO	94+70.93	1340	335	1342	31.2		36	58	1340	335	1342	31.2		36	617.3	38	22	51.4
94+70.93	TO	96+84.80	140	55	220	15.6		36	58	140	55	220	15.6		80	196.8	18	7	16.4
248+17.13	TO	251+94.32	440		286	46.8		142	306	440	0	286	46.8		142	43.4	41	0	14.5
112+49.21	TO	118+00.00	1102	275	1102					1102	275	1102				506.7	14	14	42.2
118+00.00	TO	133+00.00	3000	750	3000					3000	750	3000				1380.0	38	38	115.0
133+00.00	TO	139+23.73	1337	312	1187	31.2	66			1337	312	1187	31.2	84		573.8	19	19	47.8
144+59.61	TO	146+68.52	418	104	418					418	104	418				192.2	5	5	16.0
SUBTOTAL			10746	2537	10524					10746	2537	10524							
TOTAL			23807			156	66	214	661	23807			156	84	258	4807	239	143	411

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE. 805	SECTION 146RS-3	COUNTY ST. CLAIR	TOTAL SHEETS 21	SHEET NO. 8		
#FILE#	PLLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		
	PLLOT DATE = #DATE#	DATE - -----	REVISED - ---			CONTRACT NO. 76057						